



FEB 04 2013

Theo Blulim  
Alorica, Inc.  
5104 N. Blythe Ave.  
Fresno, CA 93722

**Re: Public Notification Requirement of California Health and Safety Code  
§42301.6  
Notice of Preliminary Decision - Authority to Construct  
Project Number: C-1130010**

Dear Mr. Blulim:

Enclosed for your review and comment is the District's analysis of Alorica, Inc.'s application for an Authority to Construct for a 1207 horsepower Tier 2 certified diesel engine to provide emergency power in the event of an electrical outage, at 5104 N. Blythe Ave. in Fresno, CA.

The notice of preliminary decision for this project will be published approximately three days from the date of this letter. Please submit your written comments on this project within the 30-day public comment period which begins on the date of publication of the public notice.

I have enclosed a copy of the California Health and Safety Code (sec. §42301.6) and the public notification letters sent out to the parents or guardians of students at Lawless Elementary School and residences within 1,000 feet of the proposed project. After the thirty day (30-day) notice period, the determination to issue the Authority to Construct can be finalized. At that time, you will also be billed for the school notice processing.

Thank you for your cooperation in this matter. If you have any questions regarding this matter, please contact Mr. Kyle Melching of Permit Services at (559) 230-5894.

Sincerely,



David Warner  
Director of Permit Services

DW:kjm

Enclosures

**Seyed Sadredin**  
Executive Director/Air Pollution Control Officer

---

**Northern Region**  
4800 Enterprise Way  
Modesto, CA 95356-8718  
Tel: (209) 557-6400 FAX: (209) 557-6475

**Central Region (Main Office)**  
1990 E. Gettysburg Avenue  
Fresno, CA 93726-0244  
Tel: (559) 230-6000 FAX: (559) 230-6061

**Southern Region**  
34946 Flyover Court  
Bakersfield, CA 93308-9725  
Tel: 661-392-5500 FAX: 661-392-5585



FEB 04 2013

Mike Tollstrup, Chief  
Project Assessment Branch  
Stationary Source Division  
California Air Resources Board  
PO Box 2815  
Sacramento, CA 95812-2815

**Re: Notice of Preliminary Decision - Authority to Construct**  
**Project Number: C-1130010**


Dear Mr. Tollstrup:

Enclosed for your review and comment is the District's analysis of Alorica, Inc.'s application for an Authority to Construct for a 1207 horsepower Tier 2 certified diesel engine to provide emergency power in the event of an electrical outage, at 5104 N. Blythe Ave. in Fresno, CA.

The notice of preliminary decision for this project will be published approximately three days from the date of this letter. Please submit your written comments on this project within the 30-day public comment period which begins on the date of publication of the public notice.

Thank you for your cooperation in this matter. If you have any questions regarding this matter, please contact Mr. Kyle Melching of Permit Services at (559) 230-5894.

Sincerely,



David Warner  
Director of Permit Services

DW:kjm

Enclosure

**Seyed Sadredin**  
Executive Director/Air Pollution Control Officer

---

**Northern Region**  
4800 Enterprise Way  
Modesto, CA 95356-8718  
Tel: (209) 557-6400 FAX: (209) 557-6475

**Central Region (Main Office)**  
1990 E. Gettysburg Avenue  
Fresno, CA 93726-0244  
Tel: (559) 230-6000 FAX: (559) 230-6061

**Southern Region**  
34946 Flyover Court  
Bakersfield, CA 93308-9725  
Tel: 661-392-5500 FAX: 661-392-5585

Fresno Bee  
Fresno Bee

**NOTICE OF PRELIMINARY DECISION  
FOR THE PROPOSED ISSUANCE OF  
AN AUTHORITY TO CONSTRUCT**

NOTICE IS HEREBY GIVEN that the San Joaquin Valley Unified Air Pollution Control District solicits public comment on the proposed issuance of Authority to Construct to Alorica, Inc. for a 1207 horsepower Tier 2 certified diesel engine to provide emergency power in the event of an electrical outage, at 5104 N. Blythe Ave. in Fresno, CA.

The analysis of the regulatory basis for this proposed action, Project #C-1130010, is available for public inspection at [http://www.valleyair.org/notices/public\\_notices\\_idx.htm](http://www.valleyair.org/notices/public_notices_idx.htm) and the District office at the address below. Written comments on this project must be submitted within 30 days of the publication date of this notice to **DAVID WARNER, DIRECTOR OF PERMIT SERVICES, SAN JOAQUIN VALLEY UNIFIED AIR POLLUTION CONTROL DISTRICT, 1990 E GETTYSBURG AVENUE, FRESNO, CA 93726.**

## HEALTH AND SAFETY CODE

### H&S 42301.6 Permit Approval: Powers & Duties of APCO

42301.6 (a) Prior to approving an application for a permit to construct or modify a source which emits hazardous air emissions, which source is located within 1,000 feet from the outer boundary of a school site, the air pollution control officer shall prepare a public notice in which the proposed project or modification for which the application for a permit is made is fully described. The notice may be prepared whether or not the material is or would be subject to subdivision (a) of Section 25536, if the air pollution control officer determines and the administering agency concurs that hazardous air emissions of the material may result from an air release, as defined by Section 44303. The notice may be combined with any other notice on the project or permit which is required by law.

(b) The air pollution control officer shall, at the permit applicant's expense, distribute or mail the public notice to the parents or guardians of children enrolled in any school that is located within one-quarter mile of the source and to each address within a radius of 1,000 feet of the proposed new or modified source at least 30 days prior to the date final action on the application is to be taken by the officer. The officer shall review and consider all comments received during the 30 days after the notice is distributed, and shall include written responses to the comments in the permit application file prior to taking final action on the application.

(1) Notwithstanding Section 49073 of the Education Code, or any other provision of law, the information necessary to mail notices required by this section shall be made available by the school district to the air pollution control officer.

(2) Nothing in this subdivision precludes, at the discretion of the air pollution control officer and with permission of the school, the distribution of the notices to the children to be given to their parents or guardians.

(c) Notwithstanding subdivision (b), an air pollution control officer may require the applicant to distribute the notice if the district had such a rule in effect prior to January 1, 1989.

(d) The requirements for public notice pursuant to subdivision (b) or a district rule in effect prior to January 1, 1989, are fulfilled if the air pollution control officer or applicant responsible for giving the notice makes a good faith effort to follow the procedures prescribed by law for giving the notice, and, in these circumstances, failure of any person to receive the notice shall not affect the validity of any permit subsequently issued by the officer.

(e) Nothing in this section shall be deemed to limit any existing authority of any District.

(f) An applicant for a permit shall certify whether the proposed source or modification is located within 1,000 feet of a school site. Misrepresentation of this fact may result in the denial of a permit.

(g) The notice requirements of this section shall not apply if the air pollution control officer determines that the application to construct or modify a source will result in a reduction or equivalent amount of air contaminants, as defined in Section 39013, or which are hazardous air emissions.

(h) As used in this section:

(1) "Hazardous air emissions" means emissions into the ambient air of air contaminants which have been identified as a toxic air contaminant by the state board or by the air pollution control officer for the jurisdiction in which the project is located. As determined by the air pollution control officer, hazardous air emissions also means emissions into the ambient air from any substances identified in subdivisions (a) to (f), inclusive, of Section 44321 of the Health and Safety Code.

(i) "Acutely hazardous material" means any material defined pursuant to subdivision (a) of Section 25532.

(amended by Stats. 1991, Ch 1183, Sec. 14.)

**San Joaquin Valley Air Pollution Control District  
Authority to Construct  
Application Review  
Diesel-Fired Emergency Standby IC Engine**

Facility Name: Alorica, Inc  
Mailing Address: 5104 N. Blythe Ave  
Fresno, CA 93722

Date: 1/7/13  
Specialist: Kyle Melching  
Lead Engineer: Esteban Gutierrez

Contact Person: T A Blulim  
Telephone: 559-276-7711  
Application #: C-8511-1-0  
Project #: C-1130010  
Complete: 1/7/13

---

**I. Proposal**

Alorica, Inc. is proposing to install a 1207 bhp (intermittent) diesel-fired emergency standby internal combustion (IC) engine powering an electrical generator.

**II. Applicable Rules**

Rule 2201 New and Modified Stationary Source Review Rule (4/21/11)  
Rule 2520 Federally Mandated Operating Permits (6/21/01)  
Rule 4001 New Source Performance Standards (4/14/99)  
Rule 4002 National Emission Standards for Hazardous Air Pollutants (5/20/04)  
Rule 4101 Visible Emissions (2/17/05)  
Rule 4102 Nuisance (12/17/92)  
Rule 4201 Particulate Matter Concentration (12/17/92)  
Rule 4701 Stationary Internal Combustion Engines – Phase 1 (8/21/03)  
Rule 4702 Stationary Internal Combustion Engines (8/18/11)  
Rule 4801 Sulfur Compounds (12/17/92)  
CH&SC 41700 Health Risk Assessment  
CH&SC 42301.6 School Notice  
Title 17 CCR, Section 93115 - Airborne Toxic Control Measure (ATCM) for Stationary Compression-Ignition (CI) Engines  
California Environmental Quality Act (CEQA)  
Public Resources Code 21000-21177: California Environmental Quality Act (CEQA)  
California Code of Regulations, Title 14, Division 6, Chapter 3, Sections 15000-15387: CEQA Guidelines

### III. Project Location

The project is located at 5104 N. Blythe Ave in Fresno, CA.

The District has verified that the equipment is located within 1,000 feet of the outer boundary of a K-12 school. Therefore, the public notification requirement of California Health and Safety Code 42301.6 is applicable to this project.

### IV. Process Description

The emergency standby engine powers an electrical generator. Other than emergency standby operation, the engine may be operated up to 50 hours per year for maintenance and testing purposes.

### V. Equipment Listing

**C-8511-1-0:** 1207 BHP (INTERMITTENT) MITSUBISHI MODEL S12A2-Y2PTAW-2 TIER 2 CERTIFIED DIESEL-FIRED EMERGENCY STANDBY IC ENGINE POWERING AN ELECTRICAL GENERATOR

### VI. Emission Control Technology Evaluation

The applicant has proposed to install a Tier 2 certified diesel-fired IC engine that is fired on very low-sulfur diesel fuel (0.0015% by weight sulfur maximum).

The proposed engine(s) meet the latest Tier Certification requirements; therefore, the engine(s) meets the latest ARB/EPA emissions standards for diesel particulate matter, hydrocarbons, nitrogen oxides, and carbon monoxide (see Appendix C for a copy of the emissions data sheet and/or the ARB/EPA executive order).

The use of very low-sulfur diesel fuel (0.0015% by weight sulfur maximum) reduces SO<sub>x</sub> emissions by over 99% from standard diesel fuel.

### VII. General Calculations

#### A. Assumptions

Emergency operating schedule:	24 hours/day
Non-emergency operating schedule:	50 hours/year
Density of diesel fuel:	7.1 lb/gal
EPA F-factor (adjusted to 60 °F):	9,051 dscf/MMBtu
Fuel heating value:	137,000 Btu/gal
BHP to Btu/hr conversion:	2,542.5 Btu/bhp-hr
Thermal efficiency of engine:	commonly ≈ 35%
PM <sub>10</sub> fraction of diesel exhaust:	0.96 (CARB, 1988)

The engine has certified NO<sub>x</sub> + VOC emissions of 4.55 g/bhp-hr. It will be assumed the NO<sub>x</sub> + VOC emission factor is split 95% NO<sub>x</sub> and 5% VOC (per the District's Carl Moyer program).

**B. Emission Factors**

Emission Factors		
Pollutant	Emission Factor (g/bhp-hr)	Source
NO <sub>x</sub>	4.32	Engine Manufacturer
SO <sub>x</sub>	0.0051	Mass Balance Equation Below
PM <sub>10</sub>	0.10	ARB/EPA Certification
CO	0.52	ARB/EPA Certification
VOC	0.23	Engine Manufacturer

$$\frac{0.000015 \text{ lb-S}}{\text{lb-fuel}} \times \frac{7.1 \text{ lb-fuel}}{\text{gallon}} \times \frac{2 \text{ lb-SO}_2}{1 \text{ lb-S}} \times \frac{1 \text{ gal}}{137,000 \text{ Btu}} \times \frac{1 \text{ bhp input}}{0.35 \text{ bhp out}} \times \frac{2,542.5 \text{ Btu}}{\text{bhp-hr}} \times \frac{453.6 \text{ g}}{\text{lb}} = 0.0051 \frac{\text{g-SO}_x}{\text{bhp-hr}}$$

**C. Calculations**

**1. Pre-Project Emissions (PE1)**

Since this is a new emissions unit, PE1 = 0.

**2. Post-Project PE (PE2)**

The daily and annual PE are calculated as follows:

Pollutant	Emissions Factor (g/bhp-hr)	Rating (bhp)	Daily Hours of Operation (hrs/day)	Annual Hours of Operation (hrs/yr)	Daily PE2 (lb/day)	Annual PE2 (lb/yr)
NO <sub>x</sub>	4.32	1207	24	50	275.9	575
SO <sub>x</sub>	0.0051	1207	24	50	0.3	1
PM <sub>10</sub>	0.10	1207	24	50	6.4	13
CO	0.52	1207	24	50	33.2	69
VOC	0.23	1207	24	50	14.7	31

**3. Pre-Project Stationary Source Potential to Emit (SSPE1)**

Pursuant to Section 4.9 of District Rule 2201, the Pre-Project Stationary Source Potential to Emit (SSPE1) is the Potential to Emit (PE) from all units with valid

ATCs or PTOs at the Stationary Source and the quantity of Emission Reduction Credits (ERCs) which have been banked since September 19, 1991 for Actual Emissions Reductions that have occurred at the source, and which have not been used on-site.

Since this is a new facility, **SSPE1 = 0 lb/yr for all criteria pollutants**

#### 4. Post-Project Stationary Source Potential to Emit (SSPE2)

Pursuant to Section 4.10 of District Rule 2201, the Post-Project Stationary Source Potential to Emit (SSPE2) is the Potential to Emit (PE) from all units with valid ATCs or PTOs, except for emissions units proposed to be shut down as part of the Stationary Project, at the Stationary Source and the quantity of Emission Reduction Credits (ERCs) which have been banked since September 19, 1991 for Actual Emissions Reductions that have occurred at the source, and which have not been used on-site.

For this project the change in emissions for the facility is due to the installation of the new emergency standby IC engine(s), permit unit -1-0. Thus:

SSPE2					
Permit Unit	NO <sub>x</sub> (lb/yr)	SO <sub>x</sub> (lb/yr)	PM <sub>10</sub> (lb/yr)	CO (lb/yr)	VOC (lb/yr)
SSPE1	0	0	0	0	0
C-8511-1-0	575	1	13	69	31
<b>SSPE2 Total</b>	<b>575</b>	<b>1</b>	<b>13</b>	<b>69</b>	<b>31</b>
<b>Offset Threshold</b>	<b>20,000</b>	<b>54,750</b>	<b>29,200</b>	<b>200,000</b>	<b>20,000</b>
<b>Offset Threshold Surpassed?</b>	<b>No</b>	<b>No</b>	<b>No</b>	<b>No</b>	<b>No</b>

#### 5. Major Source Determination

Pursuant to Section 3.24 of District Rule 2201, a Major Source is a stationary source with post project emissions or a Post Project Stationary Source Potential to Emit (SSPE2), equal to or exceeding one or more of the following threshold values. However, Section 3.24.2 states, "for the purposes of determining major source status, the SSPE2 shall not include the quantity of emission reduction credits (ERC) which have been banked since September 19, 1991 for Actual Emissions Reductions that have occurred at the source, and which have not been used on-site."

This facility does not contain ERCs which have been banked at the source; therefore, no adjustment to SSPE2 is necessary.



Major Source Determination					
Pollutant	SSPE1 (lb/yr)	SSPE2 (lb/yr)	Major Source Threshold (lb/yr)	Existing Major Source?	Becoming a Major Source?
NO <sub>x</sub>	0	575	20,000	No	No
SO <sub>x</sub>	0	1	140,000	No	No
PM <sub>10</sub>	0	13	140,000	No	No
CO	0	69	200,000	No	No
VOC	0	31	20,000	No	No

As seen in the table above, the facility is not an existing Major Source and also is not becoming a Major Source as a result of this project.

## 6. Baseline Emissions (BE)

BE = Pre-project Potential to Emit for:

- Any unit located at a non-Major Source,
- Any Highly-Utilized Emissions Unit, located at a Major Source,
- Any Fully-Offset Emissions Unit, located at a Major Source, or
- Any Clean Emissions Unit, located at a Major Source.

otherwise,

BE = Historic Actual Emissions (HAE), calculated pursuant to Section 3.23

Since this is a new emissions unit, BE = PE1 = 0 for all criteria pollutants.

## 7. SB 288 Major Modification

SB 288 Major Modification is defined in 40 CFR Part 51.165 as "any physical change in or change in the method of operation of a major stationary source that would result in a significant net emissions increase of any pollutant subject to regulation under the Act."

As discussed in Section VII.C.5 above, this facility is not a major source for any of the pollutants addressed in this project; therefore, the project does not constitute a SB 288 Major Modification.

## 8. Federal Major Modification

District Rule 2201, Section 3.18 states that Federal Major Modifications are the same as "Major Modification" as defined in 40 CFR 51.165 and part D of Title I of the CAA.

Since this facility is not a Major Source for any pollutants, this project does not constitute a Federal Major Modification. Additionally, since the facility is not a major source for PM<sub>10</sub> (140,000 lb/year), it is not a major source for PM<sub>2.5</sub> (200,000 lb/year).

### **9. Quarterly Net Emissions Change (QNEC)**

The QNEC is calculated solely to establish emissions that are used to complete the District's PAS emissions profile screen. Detailed QNEC calculations are included in Appendix E.

## **VIII. Compliance**

### **Rule 2201 New and Modified Stationary Source Review Rule**

#### **A. Best Available Control Technology (BACT)**

##### **1. BACT Applicability**

BACT requirements are triggered on a pollutant-by-pollutant basis and on an emissions unit-by-emissions unit basis for the following\*:

- a. Any new emissions unit with a potential to emit exceeding two pounds per day,
- b. The relocation from one Stationary Source to another of an existing emissions unit with a potential to emit exceeding two pounds per day,
- c. Modifications to an existing emissions unit with a valid Permit to Operate resulting in an AIPE exceeding two pounds per day, and/or
- d. Any new or modified emissions unit, in a stationary source project, which results in an SB288 Major Modification or a Federal Major Modification, as defined by the rule.

\*Except for CO emissions from a new or modified emissions unit at a Stationary Source with an SSPE2 of less than 200,000 pounds per year of CO.

As discussed in Section I, the facility is proposing to install a new emergency standby IC engine. Additionally, as determined in Sections VII.C.7 and VII.C.8, this project does not result in an SB288 Major Modification or a Federal Major Modification, respectively. Therefore, BACT can only be triggered if the daily emissions exceed 2.0 lb/day for any pollutant.

The daily emissions from the new engine are compared to the BACT threshold levels in the following table:

New Emissions Unit BACT Applicability				
Pollutant	Daily Emissions for unit -1-0 (lb/day)	BACT Threshold (lb/day)	SSPE2 (lb/yr)	BACT Triggered?
NO <sub>x</sub>	276	> 2.0	n/a	Yes
SO <sub>x</sub>	0.3	> 2.0	n/a	No
PM <sub>10</sub>	6.4	> 2.0	n/a	Yes
CO	33.2	> 2.0 and SSPE2 ≥ 200,000 lb/yr	69	No
VOC	14.7	> 2.0	n/a	Yes

As shown above, BACT will be triggered for NO<sub>x</sub>, PM<sub>10</sub>, and VOC emissions from the engine for this project.

## 2. BACT Guideline

BACT Guideline 3.1.1, which appears in Appendix B of this report, covers diesel-fired emergency IC engines.

## 3. Top Down BACT Analysis

Per District Policy APR 1305, Section IX, "A top-down BACT analysis shall be performed as a part of the Application Review for each application subject to the BACT requirements pursuant to the District's NSR Rule for source categories or classes covered in the BACT Clearinghouse, relevant information under each of the following steps may be simply cited from the Clearinghouse without further analysis."

Pursuant to the attached Top-Down BACT Analysis, which appears in Appendix B of this report, BACT is satisfied with:

- NO<sub>x</sub>: Latest EPA Tier Certification level for applicable horsepower range
- VOC: Latest EPA Tier Certification level for applicable horsepower range
- PM<sub>10</sub>: 0.15 g/hp-hr or the Latest EPA Tier Certification level for applicable horsepower range, whichever is more stringent. (ATCM)

The following condition(s) will be listed on the ATC to ensure compliance with the PM<sub>10</sub> BACT emissions limit(s):

- Emissions from this IC engine shall not exceed 0.10 g-PM10/bhp-hr based on USEPA certification using ISO 8178 test procedure. [District Rules 2201 and 4102, 17 CCR 93115, 40 CFR Part 60 Subpart IIII]

## **B. Offsets**

Since emergency IC engines are exempt from the offset requirements of Rule 2201, per Section 4.6.2, offsets are not required for this engine, and no offset calculations are required.

## **C. Public Notification**

### **1. Applicability**

Public noticing is required for:

- a. New Major Sources, SB288 Major Modifications, Federal Major Modifications

As shown in Sections VII.C.5, VII.C.7, and VII.C.8, this facility is not a new Major Source, not an SB 288 Major Modification, and not a Federal Major Modification, respectively.

- b. Any new emissions unit with a Potential to Emit greater than 100 pounds during any one day for any pollutant

As calculated in Section VII.C.2, daily emissions for NO<sub>x</sub> are greater than 100 lb/day.

- c. Any project which results in the offset thresholds being surpassed

As shown in Section VII.C.4, an offset threshold will not be surpassed.

- d. Any project with a Stationary Source Project Increase in Permitted Emissions (SSIPE) greater than 20,000 lb/year for any pollutant.

For this project, the proposed engine is the only emissions source that will generate an increase in Potential to Emit. Since the proposed engine emissions are well below 20,000 lb/year for all pollutants (See Section VII.C.2), the SSIPE for this project will be below the public notice threshold.

### **2. Public Notice Action**

As demonstrated above, this project will require public noticing. Therefore, public notice documents will be submitted to the California Air Resources Board (CARB) and a public notice will be published in a local newspaper of general circulation prior to the issuance of the ATC(s) for this equipment.

## **D. Daily Emissions Limits**

Daily Emissions Limitations (DELs) and other enforceable conditions are required by Section 3.16 to restrict a unit's maximum daily emissions, to a level at or below the emissions associated with the maximum design capacity. Per Sections 3.16.1 and 3.16.2, the DEL must be contained in the latest ATC and contained in or enforced by the latest PTO and enforceable, in a practicable manner, on a daily basis. Therefore, the following conditions will be listed on the ATC to ensure compliance:

- Emissions from this IC engine shall not exceed any of the following limits: 4.32 g-NO<sub>x</sub>/bhp-hr, 0.52 g-CO/bhp-hr, or 0.23 g-VOC/bhp-hr. [District Rule 2201, 17 CCR 93115, and 40 CFR Part 60 Subpart III]
- Emissions from this IC engine shall not exceed 0.10 g-PM<sub>10</sub>/bhp-hr based on USEPA certification using ISO 8178 test procedure. [District Rules 2201 and 4102, 17 CCR 93115, and 40 CFR Part 60 Subpart III]
- Only CARB certified diesel fuel containing not more than 0.0015% sulfur by weight is to be used. [District Rules 2201 and 4801, 17 CCR 93115, and 40 CFR Part 60 Subpart III]

## **E. Compliance Assurance**

### **1. Source Testing**

Pursuant to District Policy APR 1705, source testing is not required for emergency standby IC engines to demonstrate compliance with Rule 2201.

### **2. Monitoring**

No monitoring is required to demonstrate compliance with Rule 2201.

### **3. Recordkeeping**

Recordkeeping requirements, in accordance with District Rule 4702, will be discussed in Section VIII, *District Rule 4702*, of this evaluation.

### **4. Reporting**

No reporting is required to ensure compliance with Rule 2201.

## **F. Ambient Air Quality Analysis (AAQA)**

Section 4.14.1 of this rule requires that an ambient air quality analysis (AAQA) be conducted for the purpose of determining whether a new or modified Stationary

Source will cause or make worse a violation of an air quality standard. The Technical Services Division of the SJVAPCD conducted the required analysis.

As shown by the AAQA summary sheet in Appendix D, the proposed equipment will not cause or make worse a violation of an air quality standard for NO<sub>x</sub>, CO, PM<sub>10</sub>, or SO<sub>x</sub>.

**Rule 2520 Federally Mandated Operating Permits**

Since this facility's potential to emit does not exceed any major source thresholds of Rule 2201, this facility is not a major source, and Rule 2520 does not apply.

**Rule 4001 New Source Performance Standards (NSPS)**

**40 CFR 60 Subpart IIII – Standards of Performance for Stationary Compression Ignition Internal Combustion Engines**

The following table demonstrates how the proposed engine(s) will comply with the requirements of 40 CFR Part 60 Subpart IIII.

<b>40 CFR 60 Subpart IIII Requirements for New Emergency IC Engines Powering Generators (2007 and Later Model Year)</b>	<b>Proposed Method of Compliance with 40 CFR 60 Subpart IIII Requirements</b>
Engine(s) must meet the appropriate Subpart IIII emission standards for new engines, based on the model year, size, and number of liters per cylinder.	The applicant has proposed the use of engine(s) that are certified to the latest EPA Tier Certification level for the applicable horsepower range, guaranteeing compliance with the emission standards of Subpart IIII.
Engine(s) must be fired on 500 ppm sulfur content fuel or less, and fuel with a minimum centane index of 40 or a maximum aromatic content of 35 percent by volume. Starting in October 1, 2010, the maximum allowable sulfur fuel content will be lowered to 15 ppm.	The applicant has proposed the use of CARB certified diesel fuel, which meets all of the fuel requirements listed in Subpart IIII. A permit condition enforcing this requirement was included earlier in this evaluation.
The operator/owner must install a non-resettable hour meter prior to startup of the engine(s).	The applicant has proposed to install a non-resettable hour meter. The following condition will be included on the permit: <ul style="list-style-type: none"> <li>• This engine shall be equipped with an operational non-resettable elapsed time meter or other APCO approved alternative. [District Rule 4702, 17 CCR 93115, and 40 CFR 60 Subpart IIII]</li> </ul>
Emergency engine(s) may be operated for the purpose of maintenance and testing up to 100 hours per year. There is no limit on emergency use.	The Air Toxic Control Measure for Stationary Compression Ignition Engines (Stationary ATCM) limits this engine maintenance and testing to 50 hours/year. Thus, compliance is expected.

<p>The owner/operator must operate and maintain the engine(s) and any installed control devices according to the manufacturers written instructions.</p>	<p>The following condition will be included on the permit:</p> <ul style="list-style-type: none"><li>• This engine shall be operated and maintained in proper operating condition as recommended by the engine manufacturer or emissions control system supplier. [District Rule 4702 and 40 CFR 60 Subpart IIII]</li></ul>
--	---

## **Rule 4002 National Emission Standards for Hazardous Air Pollutants**

### **40 CFR 63 Subpart ZZZZ – National Emission Standards for Hazardous Air Pollutants for Stationary Reciprocating Internal Combustion Emissions (RICE)**

Emergency engines are subject to this subpart if they are operated at a major or area source of Hazardous Air Pollutant (HAP) emissions. A major source of HAP emissions is a facility that has the potential to emit any single HAP at a rate of 10 tons/year or greater or any combinations of HAPs at a rate of 25 tons/year or greater. An area source of HAPs is a facility is not a major source of HAPs. The proposed engine(s) are new stationary RICE located at an area source of HAP emissions; therefore, these engines are subject to this Subpart.

40 CFR 63 Subpart ZZZZ requires the following engines to comply with 40 CFR 60 Subpart IIII:

1. New emergency engines located at area sources of HAPs
2. Emergency engines rated less than or equal to 500 bhp and located at major sources of HAPs

The proposed engine(s) will be in compliance with 40 CFR 60 Subpart IIII.

Additionally, 40 CFR 63 Subpart ZZZZ requires engines rated greater 500 bhp and located at major sources of HAPs to meet the notification requirements of §63.6645(h); however, that section only applies if an initial performance test is required. Since an initial performance test is not required for emergency engines, the notification requirement is not applicable.

The proposed engines are expected to be in compliance with 40 CFR 63 Subpart ZZZZ.

## **Rule 4101 Visible Emissions**

Rule 4101 states that no air contaminant shall be discharged into the atmosphere for a period or periods aggregating more than three minutes in any one hour which is as dark

as, or darker than, Ringelmann 1 or 20% opacity. Therefore, the following condition will be listed on the ATC to ensure compliance:

- {15} No air contaminant shall be discharged into the atmosphere for a period or periods aggregating more than three minutes in any one hour which is as dark as, or darker than, Ringelmann 1 or 20% opacity. [District Rule 4101]

**Rule 4102 Nuisance**

Rule 4102 states that no air contaminant shall be released into the atmosphere which causes a public nuisance. Public nuisance conditions are not expected as a result of these operations, provided the equipment is well maintained. Therefore, the following condition will be listed on the ATC to ensure compliance:

- {98} No air contaminant shall be released into the atmosphere which causes a public nuisance. [District Rule 4102]

**California Health & Safety Code 41700 (Health Risk Assessment)**

District Policy APR 1905 - Risk Management Policy for Permitting New and Modified Sources (dated 3/2/01) specifies that for an increase in emissions associated with a proposed new source or modification, the District perform an analysis to determine the possible impact to the nearest resident or worksite. Therefore, a risk management review (RMR) was performed for this project. The RMR results are summarized in the following table, and can be seen in detail in Appendix D.

<b>RMR Results</b>				
Unit	Acute Hazard Index	Chronic Hazard Index	Cancer Risk	T-BACT Required?
C-8511-1-0	N/A	N/A	0.48 in a million	No

The following conditions will be listed on the ATC to ensure compliance with the RMR:

- {1898} The exhaust stack shall vent vertically upward. The vertical exhaust flow shall not be impeded by a rain cap (flapper ok), roof overhang, or any other obstruction. [District Rule 4102]
- Emissions from this IC engine shall not exceed 0.10 g-PM10/bhp-hr based on USEPA certification using ISO 8178 test procedure. [District Rules 2201 and 4102, 17 CCR 93115, 40 CFR Part 60 Subpart III]



**Rule 4201 Particulate Matter Concentration**

Rule 4201 limits particulate matter emissions from any single source operation to 0.1 g/dscf, which, as calculated below, is equivalent to a PM<sub>10</sub> emission factor of 0.4 g-PM<sub>10</sub>/bhp-hr.

$$0.1 \frac{\text{grain-PM}}{\text{dscf}} \times \frac{\text{g}}{15.43\text{grain}} \times \frac{1 \text{ Btu}_{in}}{0.35 \text{ Btu}_{out}} \times \frac{9,051\text{dscf}}{10^6 \text{ Btu}} \times \frac{2,542.5 \text{ Btu}}{1 \text{ bhp-hr}} \times \frac{0.96 \text{g-PM}_{10}}{1 \text{g-PM}} = 0.4 \frac{\text{g-PM}_{10}}{\text{bhp-hr}}$$

The new engine has a PM<sub>10</sub> emission factor less than 0.4 g/bhp-hr. Therefore, compliance is expected and the following condition will be listed on the ATC:

- {14} Particulate matter emissions shall not exceed 0.1 grains/dscf in concentration. [District Rule 4201]

**Rule 4701 Internal Combustion Engines – Phase 1**

The purpose of this rule is to limit the emissions of nitrogen oxides (NOx), carbon monoxide (CO), and volatile organic compounds (VOC) from internal combustion engines. Except as provided in Section 4.0, the provisions of this rule apply to any internal combustion engine, rated greater than 50 bhp, that requires a PTO.

The proposed engine(s) are also subject to District Rule 4702, Internal Combustion Engines. Since emissions limits of District Rule 4702 and all other requirements are equivalent or more stringent than District Rule 4701 requirements, compliance with District Rule 4702 requirements will satisfy requirements of District Rule 4701.

**Rule 4702 Internal Combustion Engines**

The following table demonstrates how the proposed engine(s) will comply with the requirements of District Rule 4702.

<b>District Rule 4702 Requirements Emergency Standby IC Engines</b>	<b>Proposed Method of Compliance with District Rule 4702 Requirements</b>
Operation of emergency standby engines is limited to 100 hours or less per calendar year for non-emergency purposes, verified through the use of a non-resettable elapsed operating time meter.	The Air Toxic Control Measure for Stationary Compression Ignition Engines (Stationary ATCM) limits this engine maintenance and testing to 50 hours/year. Thus, compliance is expected.
Emergency standby engines cannot be used to reduce the demand for electrical power when normal electrical power line service has not failed, or to produce power for the electrical distribution system, or in conjunction with a voluntary utility demand reduction program or interruptible power contract.	The following conditions will be included on the permit: <ul style="list-style-type: none"> <li>• {3807} An emergency situation is an unscheduled electrical power outage caused by sudden and reasonably unforeseen natural disasters or sudden and reasonably unforeseen events beyond the control of the permittee.</li> </ul>

	<p>[District Rule 4702]</p> <ul style="list-style-type: none"> <li>• {3808} This engine shall not be used to produce power for the electrical distribution system, as part of a voluntary utility demand reduction program, or for an interruptible power contract. [District Rule 4702]</li> </ul>
<p>The owner/operator must operate and maintain the engine(s) and any installed control devices according to the manufacturers written instructions.</p>	<p>A permit condition enforcing this requirement was shown earlier in the evaluation.</p>
<p>The owner/operator must monitor the operational characteristics of each engine as recommended by the engine manufacturer or emission control system supplier.</p>	<p>The following condition will be included on the permit:</p> <ul style="list-style-type: none"> <li>• {3478} During periods of operation for maintenance, testing, and required regulatory purposes, the permittee shall monitor the operational characteristics of the engine as recommended by the manufacturer or emission control system supplier (for example: check engine fluid levels, battery, cables and connections; change engine oil and filters; replace engine coolant; and/or other operational characteristics as recommended by the manufacturer or supplier). [District Rule 4702]</li> </ul>
<p>Records of the total hours of operation of the emergency standby engine, type of fuel used, purpose for operating the engine, all hours of non-emergency and emergency operation, and support documentation must be maintained. All records shall be retained for a period of at least five years, shall be readily available, and be made available to the APCO upon request.</p>	<p>The following conditions will be included on the permit:</p> <ul style="list-style-type: none"> <li>• {3496} The permittee shall maintain monthly records of emergency and non-emergency operation. Records shall include the number of hours of emergency operation, the date and number of hours of all testing and maintenance operations, the purpose of the operation (for example: load testing, weekly testing, rolling blackout, general area power outage, etc.) and records of operational characteristics monitoring. For units with automated testing systems, the operator may, as an alternative to keeping records of actual operation for testing purposes, maintain a readily accessible written record of the automated testing schedule. [District Rule 4702 and 17 CCR 93115]</li> <li>• The permittee shall maintain monthly records of the type of fuel purchased. [District Rule 4702 and 17 CCR 93115]</li> <li>• {3475} All records shall be maintained and</li> </ul>

	retained on-site for a minimum of five (5) years, and shall be made available for District inspection upon request. [District Rule 4702 and 17 CCR 93115]
--	---

**Rule 4801 Sulfur Compounds**

Rule 4801 requires that sulfur compound emissions (as SO<sub>2</sub>) shall not exceed 0.2% by volume. Using the ideal gas equation, the sulfur compound emissions are calculated as follows:

$$\text{Volume SO}_2 = (n \times R \times T) \div P$$

n = moles SO<sub>2</sub>

T (standard temperature) = 60 °F or 520 °R

$$R \text{ (universal gas constant)} = \frac{10.73 \text{ psi} \cdot \text{ft}^3}{\text{lb} \cdot \text{mol} \cdot \text{°R}}$$

$$\frac{0.000015 \text{ lb} - S}{\text{lb} - \text{fuel}} \times \frac{7.1 \text{ lb}}{\text{gal}} \times \frac{64 \text{ lb} - \text{SO}_2}{32 \text{ lb} - S} \times \frac{1 \text{ MMBtu}}{9,051 \text{ scf}} \times \frac{1 \text{ gal}}{0.137 \text{ MMBtu}} \times \frac{\text{lb} - \text{mol}}{64 \text{ lb} - \text{SO}_2} \times \frac{10.73 \text{ psi} - \text{ft}^3}{\text{lb} - \text{mol} - \text{°R}} \times \frac{520 \text{°R}}{14.7 \text{ psi}} \times 1,000,000 = 1.0 \text{ ppmv}$$

Since 1.0 ppmv is ≤ 2,000 ppmv, this engine is expected to comply with Rule 4801. Therefore, the following condition will be listed on the ATC to ensure compliance:

- Only CARB certified diesel fuel containing not more than 0.0015% sulfur by weight is to be used. [District Rules 2201 and 4801, 17 CCR 93115, and 40 CFR Part 60 Subpart III]

**California Health & Safety Code 42301.6 (School Notice)**

The District has verified that this site is located within 1,000 feet of the following school:

School Name: Lawless Elementary School  
Address: 5255 N. Reese Ave.  
Fresno, CA 93722

Therefore, pursuant to California Health and Safety Code 42301.6, a school notice is required.

Prior to the issuance of the ATC for this equipment, notices will be provided to the parents/guardians of all students of the affected school, and will be sent to all residents within 1,000 ft of the site.

The District has verified that there are no additional schools within ¼ mile of the emission source.

**Title 17 California Code of Regulations (CCR), Section 93115 - Airborne Toxic Control Measure (ATCM) for Stationary Compression-Ignition (CI) Engines**

The following table demonstrates how the proposed engine(s) will comply with the requirements of Title 17 CCR Section 93115.

<p><b>Title 17 CCR Section 93115 Requirements for New Emergency IC Engines Powering Electrical Generators</b></p>	<p><b>Proposed Method of Compliance with Title 17 CCR Section 93115 Requirements</b></p>
<p>Emergency engine(s) must be fired on CARB diesel fuel, or an approved alternative diesel fuel.</p>	<p>The applicant has proposed the use of CARB certified diesel fuel. The proposed permit condition, requiring the use of CARB certified diesel fuel, was included earlier in this evaluation.</p>
<p>The engine(s) must emit diesel PM at a rate less than or equal to 0.15 g/bhp-hr or must meet the diesel PM standard, as specified in the Off-road compression ignition standards for off-road engines with the same maximum rated power (Title 13 CCR, Section 2423).</p>	<p>The applicant has proposed the use of engine(s) that are certified to the latest EPA Tier Certification level for the applicable horsepower range, guaranteeing compliance with the emission standards of Subpart IIII. Additionally, the proposed diesel PM emissions rate is less than or equal to 0.15 g/bhp-hr.</p>
<p>The engine may not be operated more than 50 hours per year for maintenance and testing purposes.</p>	<p>The following condition will be included on the permit:</p> <ul style="list-style-type: none"> <li>• This engine shall be operated only for testing and maintenance of the engine, required regulatory purposes, and during emergency situations. Operation of the engine for maintenance, testing, and required regulatory purposes shall not exceed 50 hours per calendar year. [District Rule 4702, 17 CCR 93115 and 40 CFR Part 60 Subpart IIII]</li> </ul>
<p>New stationary emergency standby diesel-fueled CI engines (&gt; 50 bhp) must meet the standards for off-road engines of the same model year and maximum rated power as specified in the Off-Road Compression Ignition Engine Standards (title 13, CCR, section 2423).</p>	<p>The applicant has proposed the use of engine(s) that are certified to the latest EPA Tier Certification level for the applicable horsepower range.</p>
<p>Engines, with a PM10 emissions rate greater than 0.01 g/bhp-hr and located at schools, may not be operated for maintenance and testing whenever there is a school sponsored activity on the grounds. Additionally, engines located within 500 feet of school grounds may not be operated for maintenance and testing between 7:30 AM and 3:30 PM</p>	<p>The District has verified that this engine is not located within 500' of a school.</p>
<p>An owner or operator shall maintain monthly records of the following:</p>	<p>Permit conditions enforcing these requirements were shown earlier in the evaluation.</p>

emergency use hours of operation; maintenance and testing hours of operation; hours of operation for emission testing; initial start-up testing hours; hours of operation for all other uses; and the type of fuel used. All records shall be retained for a minimum of 36 months.	
--	--

### **California Environmental Quality Act (CEQA)**

The California Environmental Quality Act (CEQA) requires each public agency to adopt objectives, criteria, and specific procedures consistent with CEQA Statutes and the CEQA Guidelines for administering its responsibilities under CEQA, including the orderly evaluation of projects and preparation of environmental documents. The San Joaquin Valley Unified Air Pollution Control District (District) adopted its *Environmental Review Guidelines* (ERG) in 2001. The basic purposes of CEQA are to:

- Inform governmental decision-makers and the public about the potential, significant environmental effects of proposed activities.
- Identify the ways that environmental damage can be avoided or significantly reduced.
- Prevent significant, avoidable damage to the environment by requiring changes in projects through the use of alternatives or mitigation measures when the governmental agency finds the changes to be feasible.
- Disclose to the public the reasons why a governmental agency approved the project in the manner the agency chose if significant environmental effects are involved.

The District performed an Engineering Evaluation (this document) for the proposed project and determined that the project qualifies for ministerial approval under the District's Guideline for Expedited Application Review (GEAR). Section 21080 of the Public Resources Code exempts from the application of CEQA those projects over which a public agency exercises only ministerial approval. Therefore, the District finds that this project is exempt from the provisions of CEQA.

### **IX. Recommendation**

Pending a successful NSR Public Noticing period, issue Authority to Construct C-8511-1-0 subject to the permit conditions on the attached draft Authority to Construct in Appendix A.

Pending a successful School Noticing period, issue Authority to Construct C-8511-1-0 subject to the permit conditions on the attached draft Authority to Construct in Appendix A.

**X. Billing Information**

<b>Billing Schedule</b>			
<b>Permit Number</b>	<b>Fee Schedule</b>	<b>Fee Description</b>	<b>Fee Amount</b>
C-8511-1-0	3020-10-F	1207 bhp IC engine	\$749.00

**Appendixes**

- A. Draft ATC
- B. BACT Guideline and BACT Analysis
- C. Emissions Data Sheet
- D. HRA Summary and AAQA
- E. QNEC Calculations

Appendix A  
Draft ATC

San Joaquin Valley  
Air Pollution Control District

**AUTHORITY TO CONSTRUCT**

ISSUANCE DATE: DRAFT  
**DRAFT**

PERMIT NO: C-8511-1-0

LEGAL OWNER OR OPERATOR: ALORICA INC  
MAILING ADDRESS: 5104 N BLYTHE AVE  
FRESNO, CA 93722

LOCATION: 5104 N BLYTHE AVE  
FRESNO, CA 93722

EQUIPMENT DESCRIPTION:  
1207 BHP (INTERMITTENT) MITSUBISHI MODEL S12A2-Y2PTAW-2 TIER 2 CERTIFIED DIESEL-FIRED EMERGENCY  
STANDBY IC ENGINE POWERING AN ELECTRICAL GENERATOR

**CONDITIONS**

1. {14} Particulate matter emissions shall not exceed 0.1 grains/dscf in concentration. [District Rule 4201]
2. {15} No air contaminant shall be discharged into the atmosphere for a period or periods aggregating more than three minutes in any one hour which is as dark as, or darker than, Ringelmann 1 or 20% opacity. [District Rule 4101]
3. {98} No air contaminant shall be released into the atmosphere which causes a public nuisance. [District Rule 4102]
4. {1898} The exhaust stack shall vent vertically upward. The vertical exhaust flow shall not be impeded by a rain cap (flapper ok), roof overhang, or any other obstruction. [District Rule 4102]
5. {4257} This engine shall be equipped with an operational non-resettable elapsed time meter or other APCO approved alternative. [District Rule 4702, 17 CCR 93115, and 40 CFR 60 Subpart IIII]
6. {4258} Only CARB certified diesel fuel containing not more than 0.0015% sulfur by weight is to be used. [District Rules 2201 and 4801, 17 CCR 93115, 40 CFR Part 60 Subpart IIII]
7. Emissions from this IC engine shall not exceed any of the following limits: 4.32 g-NOx/bhp-hr, 0.52 g-CO/bhp-hr, or 0.23 g-VOC/bhp-hr. [District Rule 2201, 17 CCR 93115, and 40 CFR Part 60 Subpart IIII]
8. Emissions from this IC engine shall not exceed 0.10 g-PM10/bhp-hr based on USEPA certification using ISO 8178 test procedure. [District Rules 2201 and 4102, 17 CCR 93115, and 40 CFR Part 60 Subpart IIII]
9. {4261} This engine shall be operated and maintained in proper operating condition as recommended by the engine manufacturer or emissions control system supplier. [District Rule 4702 and 40 CFR 60 Subpart IIII]

CONDITIONS CONTINUE ON NEXT PAGE

YOU **MUST** NOTIFY THE DISTRICT COMPLIANCE DIVISION AT (559) 230-5950 WHEN CONSTRUCTION IS COMPLETED AND PRIOR TO OPERATING THE EQUIPMENT OR MODIFICATIONS AUTHORIZED BY THIS AUTHORITY TO CONSTRUCT. This is NOT a PERMIT TO OPERATE. Approval or denial of a PERMIT TO OPERATE will be made after an inspection to verify that the equipment has been constructed in accordance with the approved plans, specifications and conditions of this Authority to Construct, and to determine if the equipment can be operated in compliance with all Rules and Regulations of the San Joaquin Valley Unified Air Pollution Control District. Unless construction has commenced pursuant to Rule 2050, this Authority to Construct shall expire and application shall be cancelled two years from the date of issuance. The applicant is responsible for complying with all laws, ordinances and regulations of all other governmental agencies which may pertain to the above equipment.

Seyed Sadredin, Executive Director APCO

**DRAFT**

DAVID WARNER, Director of Permit Services

C-8511-1-0; Jan 8 2013 12:28PM - MELCHINK : Joint Inspection NOT Required



10. {3478} During periods of operation for maintenance, testing, and required regulatory purposes, the permittee shall monitor the operational characteristics of the engine as recommended by the manufacturer or emission control system supplier (for example: check engine fluid levels, battery, cables and connections; change engine oil and filters; replace engine coolant; and/or other operational characteristics as recommended by the manufacturer or supplier). [District Rule 4702]
11. {3807} An emergency situation is an unscheduled electrical power outage caused by sudden and reasonably unforeseen natural disasters or sudden and reasonably unforeseen events beyond the control of the permittee. [District Rule 4702]
12. {3808} This engine shall not be used to produce power for the electrical distribution system, as part of a voluntary utility demand reduction program, or for an interruptible power contract. [District Rule 4702]
13. {3496} The permittee shall maintain monthly records of emergency and non-emergency operation. Records shall include the number of hours of emergency operation, the date and number of hours of all testing and maintenance operations, the purpose of the operation (for example: load testing, weekly testing, rolling blackout, general area power outage, etc.) and records of operational characteristics monitoring. For units with automated testing systems, the operator may, as an alternative to keeping records of actual operation for testing purposes, maintain a readily accessible written record of the automated testing schedule. [District Rule 4702 and 17 CCR 93115]
14. {4262} This engine shall be operated only for testing and maintenance of the engine, required regulatory purposes, and during emergency situations. Operation of the engine for maintenance, testing, and required regulatory purposes shall not exceed 50 hours per calendar year. [District Rule 4702, 17 CCR 93115 and 40 CFR Part 60 Subpart IIII]
15. {4263} The permittee shall maintain monthly records of the type of fuel purchased. [District Rule 4702 and 17 CCR 93115]
16. {3475} All records shall be maintained and retained on-site for a minimum of five (5) years, and shall be made available for District inspection upon request. [District Rule 4702 and 17 CCR 93115]

DRAFT

Appendix B  
BACT Guideline and BACT Analysis

# San Joaquin Valley Unified Air Pollution Control District

**Best Available Control Technology (BACT) Guideline 3.1.1**  
**Last Update: 7/10/2009**  
**Emergency Diesel IC Engine**

Pollutant	Achieved in Practice or in the SIP	Technologically Feasible	Alternate Basic Equipment
CO	Latest EPA Tier Certification level for applicable horsepower range		
NOX	Latest EPA Tier Certification level for applicable horsepower range		
PM10	0.15 g/hp-hr or the Latest EPA Tier Certification level for applicable horsepower range, whichever is more stringent. (ATCM)		
SOX	Very low sulfur diesel fuel (15 ppmw sulfur or less)		
VOC	Latest EPA Tier Certification level for applicable horsepower range		

BACT is the most stringent control technique for the emissions unit and class of source. Control techniques that are not achieved in practice or contained in a state implementation plan must be cost effective as well as feasible. Economic analysis to demonstrate cost effectiveness is required for all determinations that are not achieved in practice or contained in an EPA approved State Implementation Plan.

## Top Down BACT Analysis for the Emergency IC Engine(s)

BACT Guideline 3.1.1 (July 10, 2009) applies to emergency diesel IC engines. In accordance with the District BACT policy, information from that guideline will be utilized without further analysis.

### 1. BACT Analysis for NO<sub>x</sub> AND VOC, Emissions:

#### a. Step 1 - Identify all control technologies

BACT Guideline 3.1.1 identifies only the following option:

- *Latest EPA Tier Certification level for applicable horsepower range*

To determine the latest applicable Tier level, the following EPA and state regulations were consulted:

- 40 CFR Part 60 Subpart IIII – Standards of Performance for Stationary Compression Ignition Internal Combustion Engines
- 40 CFR Part 89 – Control of Emissions from New and In-Use Nonroad Compression – Ignition Engines
- 40 CFR Part 1039 – Control of Emissions from New and In-Use Nonroad Compression-Ignition Engines
- Title 17 CCR, Section 93115 - Airborne Toxic Control Measure (ATCM) for Stationary Compression-Ignition (CI) Engines

40 CFR Parts 89 and 1039, which apply only to nonroad engines, do not directly apply because the proposed emergency engine(s) do not meet the definition of a nonroad engine. Therefore, only Title 17 CCR, Section 93115 and 40 CFR Part 60 Subpart IIII apply directly to the proposed emergency engine(s).

Title 17 CCR, Section 93115.6(a)(3)(A) (CARB stationary diesel engine ATCM) applies to emergency standby diesel-fired engines and requires that such engines be certified to the emission levels in Table 1 (below). Please note that these levels are at least as stringent or more stringent than the emission levels in 40 CFR Subpart IIII.

<p><b>Table 1: Emission Standards for New Stationary Emergency Standby Diesel-Fueled CI Engines g/bhp-hr (g/kW-hr)</b></p>
--

Maximum Engine Power	Tier	Model Year(s)	PM	NMHC+NO <sub>x</sub>	CO
50 ≤ HP < 75 (37 ≤ kW < 56)	2	2007	0.15 (0.20)	5.6 (7.5)	3.7 (5.0)
	4i	2008+		3.5 (4.7)	
75 ≤ HP < 100 (56 ≤ kW < 75)	2	2007	0.15 (0.20)	5.6 (7.5)	3.7 (5.0)
	3	2008+		3.5 (4.7)	
100 ≤ HP < 175 (75 ≤ kW < 130)	3	2007	0.15 (0.20)	3.0 (4.0)	3.7 (5.0)
		2008+			
175 ≤ HP < 300 (130 ≤ kW < 225)	3	2007	0.15 (0.20)	3.0 (4.0)	2.6 (3.5)
		2008+			
300 ≤ HP < 600 (225 ≤ kW < 450)	3	2007	0.15 (0.20)	3.0 (4.0)	2.6 (3.5)
		2008+			
600 ≤ HP ≤ 750 (450 ≤ kW ≤ 560)	3	2007	0.15 (0.20)	3.0 (4.0)	2.6 (3.5)
		2008+			
HP > 750 (kW > 560)	2	2007	0.15 (0.20)	4.8 (6.4)	2.6 (3.5)
		2008+			

Additionally, 40 CFR Subpart IIII establishes emission standards for emergency diesel IC engines. These emission standards are the same as those specified in the CARB ATCM, except for engines rated greater than or equal to 50 and less than 75 hp. For such IC engines, the CARB ATCM is more stringent.

Therefore, the most stringent applicable emission standards are those listed in the CARB ATCM (Table 1).

For IC engines rated greater than or equal to 50 hp and less than 75 hp the the highest Tier required is Tier 4i. For IC engines rated greater than or equal to 75 hp and less than 750 hp the highest Tier required is Tier 3. For engines rated equal to or greater than 750 hp the highest Tier required is Tier 2.

Also, please note that neither the state ATCM nor the Code of Federal Regulations require the installation of IC engines meeting a higher Tier standard than those listed above for emergency applications, due to concerns regarding the effectiveness of the exhaust emissions controls during periods of short-term operation (such as testing operational readiness of an emergency engine).

The proposed engine(s) is/are rated at 1207 hp. Therefore, the applicable control technology option is EPA Tier 2 certification.

**b. Step 2 - Eliminate technologically infeasible options**

The control option listed in Step 1 is not technologically infeasible.

**c. Step 3 - Rank remaining options by control effectiveness**

No ranking needs to be done because there is only one control option listed in Step 1.

**d. Step 4 - Cost Effectiveness Analysis**

The applicant has proposed the only control option remaining under consideration. Therefore, a cost effectiveness analysis is not required.

**e. Step 5 - Select BACT**

BACT for NO<sub>x</sub> and VOC will be the use of an EPA Tier 2 certified engine. The applicant is proposing such a unit. Therefore, BACT will be satisfied.

**3. BACT Analysis for PM<sub>10</sub> Emissions:**

**a. Step 1 - Identify all control technologies**

BACT Guideline 3.1.1 identifies only the following option:

- *0.15 g/bhp-hr or the Latest EPA Tier Certification level for applicable horsepower range, whichever is more stringent. (ATCM)*

The latest EPA Tier Certification level for an engine of the proposed model year and horsepower rating is Tier 2/3. Refer to the Top-Down BACT analysis for NO<sub>x</sub> for a discussion regarding the determination of the EPA Tier level to be considered.

Please note Tier 2 or 3 IC engines do not have a PM emission standard that is more stringent than 0.15 g/hp-hr. Additionally, the ATCM requires a PM emission standard of 0.15 g/hp-hr for all new emergency diesel IC engines.

Therefore, a PM/PM<sub>10</sub> emission standard of 0.15 g/hp-hr is required as BACT.

**b. Step 2 - Eliminate technologically infeasible options**

The control option listed in Step 1 is not technologically infeasible.

**c. Step 3 - Rank remaining options by control effectiveness**

No ranking needs to be done because there is only one control option listed in Step 1.

**d. Step 4 - Cost Effectiveness Analysis**

The applicant has proposed the only control option remaining under consideration. Therefore, a cost effectiveness analysis is not required.

**e. Step 5 - Select BACT**

BACT for PM<sub>10</sub> is emissions of 0.15 g/hp-hr or less. The applicant is proposing an engine that meets this requirement. Therefore, BACT will be satisfied.

Appendix C  
Emissions Data Sheet

 <b>AIR RESOURCES BOARD</b>	<b>MITSUBISHI HEAVY INDUSTRIES, LTD.</b>	<b>EXECUTIVE ORDER U-R-035-0223</b> New Off-Road Compression-Ignition Engines
---	--	---

Pursuant to the authority vested in the Air Resources Board by Sections 43013, 43018, 43101, 43102, 43104 and 43105 of the Health and Safety Code; and

Pursuant to the authority vested in the undersigned by Sections 39515 and 39516 of the Health and Safety Code and Executive Order G-02-003;

**IT IS ORDERED AND RESOLVED:** That the following compression-ignition engine and emission control system produced by the manufacturer are certified as described below for use in off-road equipment. Production engines shall be in all material respects the same as those for which certification is granted.

MODEL YEAR	ENGINE FAMILY	DISPLACEMENT (liters)	FUEL TYPE	USEFUL LIFE (hours)
2007	7MVXL33.9BBA	33.9	Diesel	8000
SPECIAL FEATURES & EMISSION CONTROL SYSTEMS			TYPICAL EQUIPMENT APPLICATION	
Direct Diesel Injection, Turbocharger			Generator	

The engine models and codes are attached.

The following are the exhaust certification standards (STD) and certification levels (CERT) for hydrocarbon (HC), oxides of nitrogen (NOx), or non-methane hydrocarbon plus oxides of nitrogen (NMHC+NOx), carbon monoxide (CO), and particulate matter (PM) in grams per kilowatt-hour (g/kw-hr), and the opacity-of-smoke certification standards and certification levels in percent (%) during acceleration (Accel), lugging (Lug), and the peak value from either mode (Peak) for this engine family (Title 13, California Code of Regulations, (13 CCR) Section 2423):


RATED POWER CLASS	EMISSION STANDARD CATEGORY		EXHAUST (g/kw-hr)					OPACITY (%)		
			HC	NOx	NMHC+NOx	CO	PM	ACCEL	LUG	PEAK
KW > 560	Tier 2	STD	N/A	N/A	6.4	3.5	0.20	N/A	N/A	N/A
		CERT	--	--	6.1	0.7	0.14	--	--	--

**BE IT FURTHER RESOLVED:** That for the listed engine models, the manufacturer has submitted the information and materials to demonstrate certification compliance with 13 CCR Section 2424 (emission control labels), and 13 CCR Sections 2425 and 2426 (emission control system warranty).

Engines certified under this Executive Order must conform to all applicable California emission regulations.

**This Executive Order is only granted to the engine family and model-year listed above. Engines in this family that are produced for any other model-year are not covered by this Executive Order.**

Executed at El Monte, California on this 18 day of December 2006.



Annette Hebert, Chief  
 Mobile Source Operations Division



Appendix D  
HRA Summary and AAQA

# San Joaquin Valley Air Pollution Control District Risk Management Review

To: File - Permit Services  
 From: Kyle Melching - Permit Services  
 Date: January 8, 2013  
 Facility Name: Alorica, Inc  
 Location: 5104 N. Blythe Ave., Fresno  
 Application #(s): C-8511-1-0  
 Project #: C-1130010

## A. RMR SUMMARY

RMR Summary			
Categories	Emergency Diesel ICE (Unit 1-0)	Project Totals	Facility Totals
Prioritization Score	N/A <sup>1</sup>	N/A <sup>1</sup>	>1
Acute Hazard Index	N/A <sup>2</sup>	N/A <sup>2</sup>	0.12
Chronic Hazard Index	N/A <sup>2</sup>	N/A <sup>2</sup>	0.57
Maximum Individual Cancer Risk	4.8E-07	4.8E-07	4.8E-07
T-BACT Required?	No		
Special Permit Conditions?	Yes		

- 1 Prioritization for this unit was not conducted since it has been determined that all diesel-fired IC engines will result in a prioritization score greater than 1.0.
- 2 Acute and Chronic Hazard Indices were not calculated since there is no risk factor, or the risk factor is so low that the risk has been determined to be insignificant for this type of unit.

### Proposed Permit Conditions

To ensure that human health risks will not exceed District allowable levels; the following permit conditions must be included for:

#### Unit 1-0

1. The PM10 emissions rate shall not exceed **0.10 g/bhp-hr** based on US EPA certification using ISO 8178 test procedure. [District Rules 2201]
2. The exhaust stack shall vent vertically upward. The vertical exhaust flow shall not be impeded by a rain cap (flapper ok), roof overhang, or any other obstruction. [District Rule 4102]
3. This engine shall be operated only for testing and maintenance of the engine, required regulatory purposes, and during emergency situations. Operation of the engine for maintenance, testing, and required regulatory purposes shall not exceed 50 hours per calendar year. [District Rule 4702 and 17 CCR 93115]

## B. RMR REPORT

### I. Project Description

Technical Services received a request on January 8, 2013, to perform an Ambient Air Quality Analysis (AAQA) and a Risk Management Review (RMR) for one 1207 bhp emergency diesel IC engine powering an electrical generator.

### II. Analysis

Technical Services performed screening level health risk assessments using the District developed DICE database.

The following parameters were used for the review:

Analysis Parameters Unit 1-0			
Source Type	Point	Location Type	Urban
BHP	1207	PM <sub>10</sub> g/hp-hr	0.10
Closest Receptor (m)	34	Quad	2
Max Hours per Year	50	Type of Closest Receptor	Business

Technical Services also performed modeling for criteria pollutants NO<sub>x</sub>, SO<sub>x</sub>, PM<sub>10</sub>, and PM<sub>2.5</sub>; as well as the RMR. For Unit 1-0, the emission rates used for criteria pollutant modeling were 575 lb/yr NO<sub>x</sub>, 1 lb/yr SO<sub>x</sub>, 13 lb/yr PM<sub>10</sub>, and 13 lb/yr PM<sub>2.5</sub>.

The results from the Criteria Pollutant Modeling are as follows:

#### Criteria Pollutant Modeling Results\*

Diesel ICE	1 Hour	3 Hours	8 Hours	24 Hours	Annual
CO	NA <sup>1</sup>	X	NA <sup>1</sup>	X	X
NO <sub>x</sub>	NA <sup>1</sup>	X	X	X	Pass
SO <sub>x</sub>	NA <sup>1</sup>	NA <sup>1</sup>	X	NA <sup>1</sup>	Pass
PM <sub>10</sub>	X	X	X	NA <sup>1</sup>	Pass <sup>2</sup>
PM <sub>2.5</sub>	X	X	X	NA <sup>1</sup>	Pass <sup>2</sup>

\*Results were taken from the attached PSD spreadsheet.

<sup>1</sup>The project is an intermittent source as defined in APR-1920. In accordance with APR-1920, compliance with short-term (i.e., 1-hour, 3-hour, 8-hour, and 24-hour) standards is not required.

<sup>2</sup>The criteria pollutants are below EPA's level of significance as found in 40 CFR Part 51.165 (b)(2).

### III. Conclusions

The emissions from the proposed equipment will not cause or contribute significantly to a violation of the State and National AAQS.

The cancer risk associated with the operation of the proposed diesel IC engine is less than 1.0 in a million. In accordance with the District's Risk Management Policy, the project is approved **without** Toxic Best Available Control Technology (T-BACT) for PM<sub>10</sub>.

To ensure that human health risks will not exceed District allowable levels; the permit conditions listed on page 1 of this report must be included for the proposed unit.

These conclusions are based on the data provided by the applicant and the project engineer. Therefore, this analysis is valid only as long as the proposed data and parameters do not change.

#### **IV. Attachments**

- A. RMR request from the project engineer
- B. Additional information from the applicant/project engineer
- C. Toxic emissions summary
- D. Facility Summary
- E. AAQA Summary

**AAQA for Alorica, Inc. ( C-8511-1-0 )**  
**All Values are in ug/m<sup>3</sup>**

	NOx 1 Hour	NOx Annual	CO 1 Hour	CO 8 Hour	SOx 1 Hour	SOx 3 Hour	SOx 24 Hour	SOx Annual	PM 24 Hour	PM Annual
STCK1	0.000E+00	7.366E-03	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	1.708E-05	0.000E+00	2.220E-04
Background	0.000E+00	2.678E+01	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	2.664E+01	0.000E+00	4.000E+01
<b>Facility Totals</b>	0.000E+00	2.679E+01	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	2.664E+01	0.000E+00	4.000E+01
<b>AAQS</b>	188.68	56	23000	10000	195	1300	105	80	50	30

Pass      Pass      Pass      Pass      Pass      Pass      Pass      Pass      Pass      ~~Fail~~  
*PASS*

**EPA's Significance Level (ug/m<sup>3</sup>)**

NOx 1 Hour	NOx Annual	CO 1 Hour	CO 8 Hour	SOx 1 Hour	SOx 3 Hour	SOx 24 Hour	SOx Annual	PM 24 Hour	PM Annual
0.0	1.0	2000.0	500.0	0.0	25.0	5.0	1.0	5.0	1.0

*PM 2.5*  
*Annual .3*  


---

*PASS*

# AAQA Emission (g/sec)

<i>Device</i>	NOx 1 Hour	NOx Annual	CO 1 Hour	CO 8 Hour	SOx 1 Hour	SOx 3 Hour	SOx 24 Hour	SOx Annual	PM 24 Hour	PM Annual
STCK1	0.00E+00	8.27E-03	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	1.44E-05	0.00E+00	1.87E-04

Appendix E  
QNEC Calculations

### Quarterly Net Emissions Change (QNEC)

The Quarterly Net Emissions Change is used to complete the emission profile screen for the District's PAS database. The QNEC shall be calculated as follows:

QNEC = PE2 - PE1, where:

- QNEC = Quarterly Net Emissions Change for each emissions unit, lb/qtr
- PE2 = Post-Project Potential to Emit for each emissions unit, lb/qtr
- PE1 = Pre-Project Potential to Emit for each emissions unit, lb/qtr

Since this is a new unit, PE1 = 0 for all pollutants. Thus, QNEC = PE2 (lb/qtr).

Using the PE2 (lb/yr) values calculated in Section VII.C.2, Quarterly PE2 is calculated as follows:

$$PE2_{\text{quarterly}} = PE2 \text{ (lb/yr)} \div 4 \text{ quarters/year} = \text{QNEC}$$

QNEC		
Pollutant	PE2 Total (lb/yr)	Quarterly PE2 (lb/qtr)
NO <sub>x</sub>	575	143.8
SO <sub>x</sub>	1	0.3
PM <sub>10</sub>	13	3.3
CO	69	17.3
VOC	31	7.8