



JUL 0'8 2013

Darren Anderson Centeral Cal Women's Facility P O Box 1501 Chowchilla, CA 93610-1501

Notice of Preliminary Decision - Authority to Construct Re:

Facility Number: C-252 Project Number: C-1131956

Dear Mr. Anderson:

Enclosed for your review and comment is the District's analysis of Centeral Cal Women's Facility's application for an Authority to Construct for installation of a 2,722 bhp disesel-fired emergency standby IC engine powering an electric generator, at 23370 Road 22, Chowchilla.

The notice of preliminary decision for this project will be published approximately three days from the date of this letter. After addressing all comments made during the 30day public notice period, the District intends to issue the Authority to Construct. Please submit your written comments on this project within the 30-day public comment period, as specified in the enclosed public notice.

Thank you for your cooperation in this matter. If you have any questions regarding this matter, please contact Mr. Sajjad Ahmad of Permit Services at (559) 230-5903.

Sincerely,

Director of Permit Services

DW:sa

Enclosures

Mike Tollstrup, CARB (w/ enclosure) via email CC:

> Seved Sadredin Executive Director/Air Pollution Control Officer

Southern Region

NOTICE OF PRELIMINARY DECISION FOR THE PROPOSED ISSUANCE OF AN AUTHORITY TO CONSTRUCT

NOTICE IS HEREBY GIVEN that the San Joaquin Valley Unified Air Pollution Control District solicits public comment on the proposed issuance of Authority to Construct to Centeral Cal Women's Facility for installation of a 2,722 bhp disesel-fired emergency standby IC engine powering an electric generator, at 23370 Road 22, Chowchilla.

The analysis of the regulatory basis for this proposed action, Project #C-1131956, is available for public inspection at

http://www.valleyair.org/notices/public_notices_idx.htm and at any District office. For additional information, please contact the District at (559) 230-6000. Written comments on this project must be submitted by August 12, 2013 to DAVID WARNER, DIRECTOR OF PERMIT SERVICES, SAN JOAQUIN VALLEY UNIFIED AIR POLLUTION CONTROL DISTRICT, 1990 EAST GETTYSBURG AVENUE, FRESNO, CA 93726.

San Joaquin Valley Air Pollution Control District Authority to Construct Application Review Diesel-Fired Emergency Standby IC Engine

Facility Name: Central Cal Women's Facility Date: June 27, 2013

Mailing Address: P O Box 1501 Engineer: Sajjad Ahmad

Chowchilla, CA 93610-1501 Lead Engineer: Brian Clements

Contact Person: Darren Anderson (Chief Engineer I)

Telephone: (559) 665-5531 x7912

Application #: (559) 665-6055

Project #: C-1131956

Complete: June 20, 2013

I. Proposal

Central Cal Women's Facility is applying for an Authority to Construct (ATC) to install a 2,722 bhp (intermittent) diesel-fired emergency standby internal combustion (IC) engine powering an electrical generator. This trailer mounted generator was brought into the facility in September of 2012 when permit units C-252-1 and -8 were down and needed repairs. Since the facility brought this generator set without getting an ATC first, a Notice of Violation (NOV) was issued in a recent inspection by the District's Compliance department. This ATC application is issued as a result of the NOV.

This unit will serve as a backup while repairs are made to the permit units C-252-1 and -8. Although the engine is a temporary emissions unit, but since it will be at the facility more than 180 days, it does not qualify as a temporary replacement emissions unit (TREU) according to District NSR Rule. Therefore, this engine will be considered a permanent installation.

II. Applicable Rules

Rule 2201 New and Modified Stationary Source Review Rule (4/21/11

Rule 2520 Federally Mandated Operating Permits (6/21/01)

Rule 4001 New Source Performance Standards (4/14/99)

Rule 4002 National Emission Standards for Hazardous Air Pollutants (5/20/04)

Rule 4101 Visible Emissions (2/17/05)

Rule 4102 Nuisance (12/17/92)

Rule 4201 Particulate Matter Concentration (12/17/92)

Rule 4701 Stationary Internal Combustion Engines - Phase 1 (8/21/03)

Rule 4702 Stationary Internal Combustion Engines (8/18/11)

Rule 4801 Sulfur Compounds (12/17/92)

CH&SC 41700 Health Risk Assessment

CH&SC 42301.6 School Notice

Title 17 CCR, Section 93115 - Airborne Toxic Control Measure (ATCM) for Stationary Compression-Ignition (CI) Engines

California Environmental Quality Act (CEQA)

Public Resources Code 21000-21177: California Environmental Quality Act (CEQA) California Code of Regulations, Title 14, Division 6, Chapter 3, Sections 15000-15387: CEQA Guidelines

III. Project Location

The project is located at 23370 Road 22 in Chowchilla, CA.

IV. Process Description

The emergency standby engine powers an electrical generator. Other than emergency standby operation, the engine may be operated up to 50 hours per year for maintenance and testing purposes.

V. Equipment Listing

C-252-23-0:

2,722 BHP (INTERMITTENT) CATERPILLAR MODEL 3516C TIER 2 CERTIFIED DIESEL-FIRED EMERGENCY STANDBY IC ENGINE

POWERING AN ELECTRICAL GENERATOR

VI. Emission Control Technology Evaluation

The applicant has proposed to install a Tier 2 certified diesel-fired IC engine that is fired on very low-sulfur diesel fuel (0.0015% by weight sulfur maximum).

The proposed engine(s) meet the latest Tier Certification requirements; therefore, the engine(s) meets the latest ARB/EPA emissions standards for diesel particulate matter, hydrocarbons, nitrogen oxides, and carbon monoxide (see Appendix C for a copy of the emissions data sheet and/or the ARB/EPA executive order).

The use of very low-sulfur diesel fuel (0.0015% by weight sulfur maximum) reduces SO_X emissions by over 99% from standard diesel fuel.

VII. General Calculations

A. Assumptions

Emergency operating schedule: 24 hours/day Non-emergency operating schedule: 50 hours/year Density of diesel fuel: 7.1 lb/gal

EPA F-factor (adjusted to 60 °F): 9,051 dscf/MMBtu Fuel heating value: 137,000 Btu/gal BHP to Btu/hr conversion: 2,542.5 Btu/bhp-hr Thermal efficiency of engine: commonly $\approx 35\%$ PM₁₀ fraction of diesel exhaust: 0.96 (CARB, 1988)

The engine has certified NO_X + VOC emissions of 4.0 g/bhp-hr. It will be assumed the NOx + VOC emission factor is split 95% NOx and 5% VOC (per the District's Carl Moyer program).

B. Emission Factors

Emission Factors					
Pollutant	Emission Factor (g/bhp-hr)	Source			
NO _x	3.8	Engine Manufacturer			
SO _X	0.0051	Mass Balance Equation Below			
PM ₁₀	0.11	ARB/EPA Certification			
CO	1.0	ARB/EPA Certification			
VOC	0.2	Engine Manufacturer			

$$\frac{0.000015 \ lb - S}{lb - fuel} \times \frac{7.1 \ lb - fuel}{gallon} \times \frac{2 \ lb - SO_2}{1 \ lb - S} \times \frac{1 \ gal}{137,000 \ Btu} \times \frac{1 \ bhp \ input}{0.35 \ bhp \ out} \times \frac{2,542.5 \ Btu}{bhp - hr} \times \frac{453.6 \ g}{lb} = 0.0051 \qquad \frac{g - SO_x}{bhp - hr}$$

C. Calculations

1. Pre-Project Emissions (PE1)

Since this is a new emissions unit, PE1 = 0.

2. Post-Project PE (PE2)

The daily and annual PE are calculated as follows:

Pollutant	Emissions Factor (g/bhp- hr)	Rating (bhp)	Daily Hours of Operation (hrs/day)	Annual Hours of Operation (hrs/yr)	Daily PE2 (lb/day)	Annual PE2 (lb/yr)
NO _X	3.80	2,722	24	50	547.3	1,140
SO _X	0.0051	2,722	24	50	0.7	2
PM ₁₀	0.11	2,722	24	50	15.8	33
СО	1.00	2,722	24	50	144.0	300
VOC	0.20	2,722	24	50	28.8	60

3. Pre-Project Stationary Source Potential to Emit (SSPE1)

Pursuant to Section 4.9 of District Rule 2201, the Pre-Project Stationary Source Potential to Emit (SSPE1) is the Potential to Emit (PE) from all units with valid ATCs or PTOs at the Stationary Source and the quantity of Emission Reduction Credits (ERCs) which have been banked since September 19, 1991 for Actual Emissions Reductions that have occurred at the source, and which have not been used on-site.

SSPE1 is taken from project C-1103729 and summarized in the following table:

SSPE1						
Permit Unit	Description	NOx	SOx	PM10	CO	voc
C-252-1-1	emergency IC engine	145	2	7	24	1 1
C-252-2-1	emergency IC engine	995	63	71	214	80
C-252-4-0	motor vehicle coating	0	0	55	0	7,556
C-252-6-1	Printing operation	0	0	0	0	1,825
C-252-8-1	emergency IC engine	145	2	7	24	1
C-252-9-0	emergency IC engine	602	78	80	253	94
C-252-12-0	emergency IC engine	2,331	149	165	501	188
C-252-13-0	emergency IC engine	208	13	15	45	17
C-252-14-0	14-0 wood working operation		0	4,417	0	0
C-252-15-0	gasoline dispensing	0	0	0	0	1,716
C-252-22-0	Wood working operation	0	0	4,417	0	0
S	SSPE1 (lb/year)			9,234	1061	11,478

4. Post-Project Stationary Source Potential to Emit (SSPE2)

Pursuant to Section 4.10 of District Rule 2201, the Post-Project Stationary Source Potential to Emit (SSPE2) is the Potential to Emit (PE) from all units with valid ATCs or PTOs, except for emissions units proposed to be shut down as part of the Stationary Project, at the Stationary Source and the quantity of Emission Reduction Credits (ERCs) which have been banked since September 19, 1991 for Actual Emissions Reductions that have occurred at the source, and which have not been used on-site.

For this project the change in emissions for the facility is due to the installation of the new emergency standby IC engine(s), permit unit -23-0. Thus:

SSPE2					
Permit Unit	NO _x (lb/yr)	SO _X (lb/yr)	PM ₁₀ (lb/yr)	CO (lb/yr)	VOC (lb/yr)
SSPE1	4,426	307	9,234	1061	11,478
C-252-23-0	1,140	2	33	300	60
SSPE2 Total	5,566	309	9,267	1,361	11,538
Offset Threshold	20,000	54,750	29,200	200,000	20,000
Offset Threshold Surpassed?	No	No	No	No	No

5. Major Source Determination

Pursuant to Section 3.24 of District Rule 2201, a Major Source is a stationary source with post project emissions or a Post Project Stationary Source Potential to Emit (SSPE2), equal to or exceeding one or more of the following threshold values. However, Section 3.24.2 states, "for the purposes of determining major source status, the SSPE2 shall not include the quantity of emission reduction credits (ERC) which have been banked since September 19, 1991 for Actual Emissions Reductions that have occurred at the source, and which have not been used on-site."

This facility does not contain ERCs which have been banked at the source; therefore, no adjustment to SSPE2 is necessary.

	Major Source Determination				
Pollutant	SSPE1 (lb/yr)	SSPE2 (lb/yr)	Major Source Threshold (lb/yr)	Existing Major Source?	Becoming a Major Source?
NO _X	4,426	5,566	20,000	No	No
SO _X	307	309	140,000	No	No
PM ₁₀	9,234	9,267	140,000	No	No
СО	1,061	1,361	200,000	No	No
VOC	11,478	11,538	20,000	No	No

As seen in the table above, the facility is not an existing Major Source and also is not becoming a Major Source as a result of this project.

6. Baseline Emissions (BE)

BE = Pre-project Potential to Emit for:

- Any unit located at a non-Major Source,
- Any Highly-Utilized Emissions Unit, located at a Major Source,
- Any Fully-Offset Emissions Unit, located at a Major Source, or
- Any Clean Emissions Unit, located at a Major Source.

otherwise,

BE = Historic Actual Emissions (HAE), calculated pursuant to Section 3.23

Since this is a new emissions unit, BE = PE1 = 0 for all criteria pollutants.

7. SB 288 Major Modification

SB 288 Major Modification is defined in 40 CFR Part 51.165 as "any physical change in or change in the method of operation of a major stationary source that would result in a significant net emissions increase of any pollutant subject to regulation under the Act."

As discussed in Section VII.C.5 above, this facility is not a major source for any of the pollutants addressed in this project; therefore, the project does not constitute a SB 288 Major Modification.

8. Federal Major Modification

District Rule 2201, Section 3.18 states that Federal Major Modifications are the same as "Major Modification" as defined in 40 CFR 51.165 and part D of Title I of the CAA.

Since this facility is not a Major Source for any pollutants, this project does not constitute a Federal Major Modification. Additionally, since the facility is not a major source for PM_{10} (140,000 lb/year), it is not a major source for $PM_{2.5}$ (200,000 lb/year).

9. Quarterly Net Emissions Change (QNEC)

The QNEC is calculated solely to establish emissions that are used to complete the District's PAS emissions profile screen. Detailed QNEC calculations are included in Appendix E.

VIII. Compliance

Rule 2201 New and Modified Stationary Source Review Rule

A. Best Available Control Technology (BACT)

1. BACT Applicability

BACT requirements are triggered on a pollutant-by-pollutant basis and on an emissions unit-by-emissions unit basis for the following*:

- a. Any new emissions unit with a potential to emit exceeding two pounds per day,
- b. The relocation from one Stationary Source to another of an existing emissions unit with a potential to emit exceeding two pounds per day.
- c. Modifications to an existing emissions unit with a valid Permit to Operate resulting in an AIPE exceeding two pounds per day, and/or
- d. Any new or modified emissions unit, in a stationary source project, which results in an SB288 Major Modification or a Federal Major Modification, as defined by the rule.

*Except for CO emissions from a new or modified emissions unit at a Stationary Source with an SSPE2 of less than 200,000 pounds per year of CO.

As discussed in Section I, the facility is proposing to install a new emergency standby IC engine. Additionally, as determined in Sections VII.C.7 and VII.C.8, this project does not result in an SB288 Major Modification or a Federal Major Modification, respectively. Therefore, BACT can only be triggered if the daily emissions exceed 2.0 lb/day for any pollutant.

The daily emissions from the new engine are compared to the BACT threshold levels in the following table:

	New Emissions Unit BACT Applicability					
Pollutant	Daily Emissions for unit -23-0 (lb/day)	BACT Threshold (lb/day)	SSPE2 (lb/yr)	BACT Triggered?		
NO _x	547.3	> 2.0	n/a	Yes		
SO _x	0.7	> 2.0	n/a	No		
PM ₁₀	15.8	> 2.0	n/a	Yes		
СО	144.0	> 2.0 and SSPE2 ≥ 200,000 lb/yr	1,361	No		
VOC	28.8	> 2.0	n/a	Yes		

As shown above, BACT will be triggered for NO_X , PM_{10} , and VOC emissions from the engine for this project.

2. BACT Guideline

BACT Guideline 3.1.1, which appears in Appendix B of this report, covers dieselfired emergency IC engines.

3. Top Down BACT Analysis

Per District Policy APR 1305, Section IX, "A top-down BACT analysis shall be performed as a part of the Application Review for each application subject to the BACT requirements pursuant to the District's NSR Rule for source categories or classes covered in the BACT Clearinghouse, relevant information under each of the following steps may be simply cited from the Clearinghouse without further analysis."

Pursuant to the attached Top-Down BACT Analysis, which appears in Appendix B of this report, BACT is satisfied with:

NO_x: Latest EPA Tier Certification level for applicable horsepower range
 VOC: Latest EPA Tier Certification level for applicable horsepower range
 PM₁₀: 0.15 g/hp-hr or the Latest EPA Tier Certification level for applicable horsepower range, whichever is more stringent. (ATCM)

The following condition will be listed on the ATC to ensure compliance with the PM_{10} BACT emissions limit:

 Emissions from this IC engine shall not exceed 0.11 g-PM10/bhp-hr based on USEPA certification using ISO 8178 test procedure. [District Rules 2201 and 4102, 17 CCR 93115, 40 CFR Part 60 Subpart IIII]

B. Offsets

Since emergency IC engines are exempt from the offset requirements of Rule 2201, per Section 4.6.2, offsets are not required for this engine, and no offset calculations are required.

C. Public Notification

1. Applicability

Public noticing is required for:

a. New Major Sources, SB288 Major Modifications, Federal Major Modifications

As shown in Sections VII.C.5, VII.C.7, and VII.C.8, this facility is not a new Major Source, not an SB 288 Major Modification, and not a Federal Major Modification, respectively.

b. Any new emissions unit with a Potential to Emit greater than 100 pounds during any one day for any pollutant

As calculated in Section VII.C.2, daily emissions for NO_X emissions are greater than 100 lb/day.

c. Any project which results in the offset thresholds being surpassed

As shown in Section VII.C.4, an offset threshold will not be surpassed.

d. Any project with a Stationary Source Project Increase in Permitted Emissions (SSIPE) greater than 20,000 lb/year for any pollutant.

For this project, the proposed engine is the only emissions source that will generate an increase in Potential to Emit. Since the proposed engine emissions are well below 20,000 lb/year for all pollutants (See Section VII.C.2), the SSIPE for this project will be below the public notice threshold.

2. Public Notice Action

As demonstrated above, this project will require public noticing. Therefore, public notice documents will be submitted to the California Air Resources Board (CARB) and a public notice will be published in a local newspaper of general circulation prior to the issuance of the ATC(s) for this equipment.

D. Daily Emissions Limits

Daily Emissions Limitations (DELs) and other enforceable conditions are required by Section 3.16 to restrict a unit's maximum daily emissions, to a level at or below the emissions associated with the maximum design capacity. Per Sections 3.16.1 and 3.16.2, the DEL must be contained in the latest ATC and contained in or enforced by the latest PTO and enforceable, in a practicable manner, on a daily basis. Therefore, the following conditions will be listed on the ATC to ensure compliance:

- Emissions from this IC engine shall not exceed any of the following limits: 3.8 g-NOx/bhp-hr, 1.0 g-CO/bhp-hr, or 0.2 g-VOC/bhp-hr. [District Rule 2201, 17 CCR 93115, and 40 CFR Part 60 Subpart IIII]
- Emissions from this IC engine shall not exceed 0.11 g-PM10/bhp-hr based on USEPA certification using ISO 8178 test procedure. [District Rules 2201 and 4102, 17 CCR 93115, and 40 CFR Part 60 Subpart IIII]
- Only CARB certified diesel fuel containing not more than 0.0015% sulfur by weight is to be used. [District Rules 2201 and 4801, 17 CCR 93115, and 40 CFR Part 60 Subpart IIII]

E. Compliance Assurance

1. Source Testing

Pursuant to District Policy APR 1705, source testing is not required for emergency standby IC engines to demonstrate compliance with Rule 2201.

2. Monitoring

No monitoring is required to demonstrate compliance with Rule 2201.

3. Recordkeeping

Recordkeeping requirements, in accordance with District Rule 4702, will be discussed in Section VIII, *District Rule 4702*, of this evaluation.

4. Reporting

No reporting is required to ensure compliance with Rule 2201.

F. Ambient Air Quality Analysis (AAQA)

An AAQA shall be conducted for the purpose of determining whether a new or modified Stationary Source will cause or make worse a violation of an air quality standard. The District's Technical Services Division conducted the required analysis. Refer to **Appendix D** of this document for the AAQA summary sheet.

The proposed location is in an attainment area for NO_X , CO, and SO_X . As shown by the AAQA summary sheet the proposed equipment will not cause a violation of an air quality standard for NO_X , CO, or SO_X .

The proposed location is in a non-attainment area for the state's PM_{10} as well as federal and state $PM_{2.5}$ thresholds. As shown by the AAQA summary sheet the proposed equipment will not cause a violation of an air quality standard for PM_{10} and $PM_{2.5}$.

Rule 2520 Federally Mandated Operating Permits

Since this facility's potential to emit does not exceed any major source thresholds of Rule 2201, this facility is not a major source, and Rule 2520 does not apply.

Rule 4001 New Source Performance Standards (NSPS)

40 CFR 60 Subpart IIII – Standards of Performance for Stationary Compression Ignition Internal Combustion Engines

The following table demonstrates how the proposed engine(s) will comply with the requirements of 40 CFR Part 60 Subpart IIII.

40 CFR 60 Subpart IIII Requirements for New Emergency IC Engines Powering Generators (2007 and Later Model Year)	Proposed Method of Compliance with 40 CFR 60 Subpart IIII Requirements
Engine(s) must meet the appropriate Subpart IIII emission standards for new engines, based on the model year, size, and number of liters per cylinder.	The applicant has proposed the use of engine(s) that are certified to the latest EPA Tier Certification level for the applicable horsepower range, guaranteeing compliance with the emission standards of Subpart IIII.
Engine(s) must be fired on 500 ppm sulfur content fuel or less, and fuel with a minimum centane index of 40 or a maximum aromatic content of 35 percent by volume. Starting in October 1, 2010, the maximum allowable sulfur fuel content will be lowered to 15 ppm.	The applicant has proposed the use of CARB certified diesel fuel, which meets all of the fuel requirements listed in Subpart IIII. A permit condition enforcing this requirement was included earlier in this evaluation.
The operator/owner must install a non-resettable hour meter prior to startup of the engine(s).	The applicant has proposed to install a non-resettable hour meter. The following condition will be included on the permit: This engine shall be equipped with an

	operational non-resettable elapsed time meter or other APCO approved alternative. [District Rule 4702, 17 CCR 93115, and 40 CFR 60 Subpart IIII]
Emergency engine(s) may be operated for the purpose of maintenance and testing up to 100 hours per year. There is no limit on emergency use.	The Air Toxic Control Measure for Stationary Compression Ignition Engines (Stationary ATCM) limits this engine maintenance and testing to 50 hours/year. Thus, compliance is expected.
The owner/operator must operate and maintain the engine(s) and any installed control devices according to the manufacturers written instructions.	The following condition will be included on the permit: This engine shall be operated and maintained in proper operating condition as recommended by the engine manufacturer or emissions control system supplier. [District Rule 4702 and 40 CFR 60 Subpart IIII]

Rule 4002 National Emission Standards for Hazardous Air Pollutants

40 CFR 63 Subpart ZZZZ – National Emission Standards for Hazardous Air Pollutants for Stationary Reciprocating Internal Combustion Emissions (RICE)

Emergency engines are subject to this subpart if they are operated at a major or area source of Hazardous Air Pollutant (HAP) emissions. A major source of HAP emissions is a facility that has the potential to emit any single HAP at a rate of 10 tons/year or greater or any combinations of HAPs at a rate of 25 tons/year or greater. An area source of HAPs is a facility is not a major source of HAPs. The proposed engine(s) are new stationary RICE located at an area source of HAP emissions; therefore, these engines are subject to this Subpart.

40 CFR 63 Subpart ZZZZ requires the following engines to comply with 40 CFR 60 Subpart IIII:

- 1. New emergency engines located at area sources of HAPs
- 2. Emergency engines rated less than or equal to 500 bhp and located at major sources of HAPs

The proposed engine(s) will be in compliance with 40 CFR 60 Subpart IIII.

Additionally, 40 CFR 63 Subpart ZZZZ requires engines rated greater 500 bhp and located at major sources of HAPs to meet the notification requirements of §63.6645(h); however, that section only applies if an initial performance test is required. Since an initial performance test is not required for emergency engines, the notification requirement is not applicable.

The proposed engines are expected to be in compliance with 40 CFR 63 Subpart ZZZZ.

Rule 4101 Visible Emissions

Rule 4101 states that no air contaminant shall be discharged into the atmosphere for a period or periods aggregating more than three minutes in any one hour which is as dark as, or darker than, Ringelmann 1 or 20% opacity. Therefore, the following condition will be listed on the ATC to ensure compliance:

• {15} No air contaminant shall be discharged into the atmosphere for a period or periods aggregating more than three minutes in any one hour which is as dark as, or darker than, Ringelmann 1 or 20% opacity. [District Rule 4101]

Rule 4102 Nuisance

Rule 4102 states that no air contaminant shall be released into the atmosphere which causes a public nuisance. Public nuisance conditions are not expected as a result of these operations, provided the equipment is well maintained. Therefore, the following condition will be listed on the ATC to ensure compliance:

 {98} No air contaminant shall be released into the atmosphere which causes a public nuisance. [District Rule 4102]

California Health & Safety Code 41700 (Health Risk Assessment)

District Policy APR 1905 - Risk Management Policy for Permitting New and Modified Sources (dated 3/2/01) specifies that for an increase in emissions associated with a proposed new source or modification, the District perform an analysis to determine the possible impact to the nearest resident or worksite. Therefore, a risk management review (RMR) was performed for this project. The RMR results are summarized in the following table, and can be seen in detail in Appendix D.

RMR Results				
Unit	Acute Hazard Index	Chronic Hazard Index	Cancer Risk	T-BACT Required?
C-252-23-0	N/A	N/A	0.12 in a million	No

The following conditions will be listed on the ATC to ensure compliance with the RMR:

 {1898} The exhaust stack shall vent vertically upward. The vertical exhaust flow shall not be impeded by a rain cap (flapper ok), roof overhang, or any other obstruction. [District Rule 4102] Emissions from this IC engine shall not exceed 0.11 g-PM10/bhp-hr based on USEPA certification using ISO 8178 test procedure. [District Rules 2201 and 4102, 17 CCR 93115, 40 CFR Part 60 Subpart IIII]

Rule 4201 Particulate Matter Concentration

Rule 4201 limits particulate matter emissions from any single source operation to 0.1 g/dscf, which, as calculated below, is equivalent to a PM_{10} emission factor of 0.4 g- PM_{10} /bhp-hr.

$$0.1 \quad \frac{grain - PM}{dscf} \times \frac{g}{15.43grain} \times \frac{1}{0.35} \frac{Btu_{in}}{Btu_{out}} \times \frac{9,051dscf}{10^6} \times \frac{2,542.5}{1} \frac{Btu}{bhp - hr} \times \frac{0.96g - PM_{10}}{1g - PM} = 0.4 \frac{g - PM_{10}}{bhp - hr}$$

The new engine has a PM_{10} emission factor less than 0.4 g/bhp-hr. Therefore, compliance is expected and the following condition will be listed on the ATC:

 {14} Particulate matter emissions shall not exceed 0.1 grains/dscf in concentration. [District Rule 4201]

Rule 4701 Internal Combustion Engines - Phase 1

The purpose of this rule is to limit the emissions of nitrogen oxides (NOx), carbon monoxide (CO), and volatile organic compounds (VOC) from internal combustion engines. Except as provided in Section 4.0, the provisions of this rule apply to any internal combustion engine, rated greater than 50 bhp, that requires a PTO.

The proposed engine(s) are also subject to District Rule 4702, Internal Combustion Engines. Since emissions limits of District Rule 4702 and all other requirements are equivalent or more stringent than District Rule 4701 requirements, compliance with District Rule 4702 requirements will satisfy requirements of District Rule 4701.

Rule 4702 Internal Combustion Engines

The following table demonstrates how the proposed engine(s) will comply with the requirements of District Rule 4702.

District Rule 4702 Requirements Emergency Standby IC Engines	Proposed Method of Compliance with District Rule 4702 Requirements
Operation of emergency standby engines is limited to 100 hours or less per calendar year for non-emergency purposes, verified through the use of a non-resettable elapsed operating time meter.	The Air Toxic Control Measure for Stationary Compression Ignition Engines (Stationary ATCM) limits this engine maintenance and testing to 50 hours/year. Thus, compliance is expected.
Emergency standby engines cannot be used to reduce the demand for electrical power when normal electrical power line	The following conditions will be included on the permit: • {3807} An emergency situation is an

service has not failed, or to produce power for the electrical distribution system, or in conjunction with a voluntary utility demand reduction program or interruptible power contract.	unscheduled electrical power outage caused by sudden and reasonably unforeseen natural disasters or sudden and reasonably unforeseen events beyond the control of the permittee. [District Rule 4702] • {3808} This engine shall not be used to produce power for the electrical distribution system, as part of a voluntary utility demand reduction program, or for an interruptible power contract. [District Rule 4702]
The owner/operator must operate and maintain the engine(s) and any installed control devices according to the manufacturers written instructions.	A permit condition enforcing this requirement was shown earlier in the evaluation.
The owner/operator must monitor the operational characteristics of each engine as recommended by the engine manufacturer or emission control system supplier.	 The following condition will be included on the permit: {3478} During periods of operation for maintenance, testing, and required regulatory purposes, the permittee shall monitor the operational characteristics of the engine as recommended by the manufacturer or emission control system supplier (for example: check engine fluid levels, battery, cables and connections; change engine oil and filters; replace engine coolant; and/or other operational characteristics as recommended by the manufacturer or supplier). [District Rule 4702]
Records of the total hours of operation of the emergency standby engine, type of fuel used, purpose for operating the engine, all hours of non-emergency and emergency operation, and support documentation must be maintained. All records shall be retained for a period of at least five years, shall be readily available, and be made available to the APCO upon request.	The following conditions will be included on the permit: • {3496} The permittee shall maintain monthly records of emergency and non-emergency operation. Records shall include the number of hours of emergency operation, the date and number of hours of all testing and maintenance operations, the purpose of the operation (for example: load testing, weekly testing, rolling blackout, general area power outage, etc.) and records of operational characteristics monitoring. For units with automated testing systems, the operator may, as an alternative to keeping records of actual operation for testing purposes, maintain a readily accessible written record of the automated testing schedule. [District Rule 4702 and 17 CCR 93115]
	 The permittee shall maintain monthly records of the type of fuel purchased. [District Rule 4702

and 1	17	CCR	931	151	
-------	----	-----	-----	-----	--

 {3475} All records shall be maintained and retained on-site for a minimum of five (5) years, and shall be made available for District inspection upon request. [District Rule 4702 and 17 CCR 93115]

Rule 4801 Sulfur Compounds

Rule 4801 requires that sulfur compound emissions (as SO₂) shall not exceed 0.2% by volume. Using the ideal gas equation, the sulfur compound emissions are calculated as follows:

Volume $SO_2 = (n \times R \times T) \div P$ $n = moles SO_2$ T (standard temperature) = 60 °F or 520 °R R (universal gas constant) = $\frac{10.73 \, psi \cdot ft^3}{lb \cdot mol \cdot °R}$

$$\frac{0.000015 \, lb - S}{lb - fuel} \times \frac{7.1 \, lb}{gal} \times \frac{64 \, lb - SO_2}{32 \, lb + S} \times \frac{1 \, MMBtu}{9.051 \, scf} \times \frac{1 \, gal}{0.137 \, MMBtu} \times \frac{lb - mol}{64 \, lb - SO_2} \times \frac{10.73 \, psi - ft^3}{lb - mol - °R} \times \frac{520 ^{\circ}R}{14.7 \, psi} \times 1,000,000 = 1.0 \, ppmv$$

Since 1.0 ppmv is \leq 2,000 ppmv, this engine is expected to comply with Rule 4801. Therefore, the following condition will be listed on the ATC to ensure compliance:

 Only CARB certified diesel fuel containing not more than 0.0015% sulfur by weight is to be used. [District Rules 2201 and 4801, 17 CCR 93115, and 40 CFR Part 60 Subpart IIII]


California Health & Safety Code 42301.6 (School Notice)

The District has verified that this site is not located within 1,000 feet of a school. Therefore, pursuant to California Health and Safety Code 42301.6, a school notice is not required.

Title 17 California Code of Regulations (CCR), Section 93115 - Airborne Toxic Control Measure (ATCM) for Stationary Compression-Ignition (CI) Engines

The following table demonstrates how the proposed engine(s) will comply with the requirements of Title 17 CCR Section 93115.

Title 17 CCR Section 93115 Requirements for New Emergency IC Engines Powering Electrical Generators	Proposed Method of Compliance with Title 17 CCR Section 93115 Requirements
Emergency engine(s) must be fired on CARB diesel fuel, or an approved alternative diesel fuel.	The applicant has proposed the use of CARB certified diesel fuel. The proposed permit condition, requiring the use of CARB certified diesel fuel, was included earlier in this evaluation.
The engine(s) must emit diesel PM at a rate less than or equal to 0.15 g/bhp-hr or must meet the diesel PM standard, as specified in the Off-road compression ignition standards for off-road engines with the same maximum rated power (Title 13 CCR, Section 2423).	The applicant has proposed the use of engine(s) that are certified to the latest EPA Tier Certification level for the applicable horsepower range, guaranteeing compliance with the emission standards of Subpart IIII. Additionally, the proposed diesel PM emissions rate is less than or equal to 0.15 g/bhp-hr.
The engine may not be operated more than 50 hours per year for maintenance and testing purposes.	 The following condition will be included on the permit: This engine shall be operated only for testing and maintenance of the engine, required regulatory purposes, and during emergency situations. Operation of the engine for maintenance, testing, and required regulatory purposes shall not exceed 50 hours per calendar year. [District Rule 4702, 17 CCR 93115 and 40 CFR Part 60 Subpart IIII]
New stationary emergency standby diesel- fueled CI engines (> 50 bhp) must meet the standards for off-road engines of the same model year and maximum rated power as specified in the Off-Road Compression Ignition Engine Standards (title 13, CCR, section 2423).	The applicant has proposed the use of engine(s) that are certified to the latest EPA Tier Certification level for the applicable horsepower range.
Engines, with a PM10 emissions rate greater than 0.01 g/bhp-hr and located at schools, may not be operated for maintenance and testing whenever there is a school sponsored activity on the grounds. Additionally, engines located within 500 feet of school grounds may not be operated for maintenance and testing between 7:30 AM and 3:30 PM	The District has verified that this engine is not located within 500' of a school.
An owner or operator shall maintain monthly records of the following:	Permit conditions enforcing these requirements were shown earlier in the evaluation.



California Environmental Quality Act (CEQA)

The California Environmental Quality Act (CEQA) requires each public agency to adopt objectives, criteria, and specific procedures consistent with CEQA Statutes and the CEQA Guidelines for administering its responsibilities under CEQA, including the orderly evaluation of projects and preparation of environmental documents. The San Joaquin Valley Unified Air Pollution Control District (District) adopted its *Environmental Review Guidelines* (ERG) in 2001. The basic purposes of CEQA are to:

- Inform governmental decision-makers and the public about the potential, significant environmental effects of proposed activities.
- Identify the ways that environmental damage can be avoided or significantly reduced.
- Prevent significant, avoidable damage to the environment by requiring changes in projects through the use of alternatives or mitigation measures when the governmental agency finds the changes to be feasible.
- Disclose to the public the reasons why a governmental agency approved the project in the manner the agency chose if significant environmental effects are involved.

The District performed an Engineering Evaluation (this document) for the proposed project and determined that the project qualifies for ministerial approval under the District's Guideline for Expedited Application Review (GEAR). Section 21080 of the Public Resources Code exempts from the application of CEQA those projects over which a public agency exercises only ministerial approval. Therefore, the District finds that this project is exempt from the provisions of CEQA.

IX. Recommendation

Pending a successful NSR Public Noticing period, issue Authority to Construct C-252-23-0 subject to the permit conditions on the attached draft Authority to Construct in Appendix A.

X. Billing Information

Billing Schedule									
Permit Number Fee Schedule Fee Description Fee Amount									
C-252-23-0	3020-10-F	2,722 bhp IC engine	\$749.00						

Appendixes

- A. Draft ATC
- B. BACT Guideline and BACT Analysis
- C. Emissions Data Sheet
- D. HRA Summary and AAQA
- E. QNEC Calculations

Appendix A

Draft ATC

San Joaquin Valley Air Pollution Control District

AUTHORITY TO CONSTRUCT

ISSUÀ

PERMIT NO: C-252-23-0

LEGAL OWNER OR OPERATOR: CENTRAL CAL WOMEN'S FACILITY

MAILING ADDRESS:

PO BOX 1501

CHOWCHILLA, CA 93610-1501

LOCATION:

23370 ROAD 22

CHOWCHILLA, CA 93610

EQUIPMENT DESCRIPTION:

2,722 BHP (INTERMITTENT) CATERPILLAR MODEL 3516C TIER 2 CERTIFIED DIESEL-FIRED EMERGENCY STANDBY IC ENGINE POWERING AN ELECTRICAL GENERATOR

CONDITIONS

- 1. {14} Particulate matter emissions shall not exceed 0.1 grains/dscf in concentration. [District Rule 4201]
- 2. {15} No air contaminant shall be discharged into the atmosphere for a period or periods aggregating more than three minutes in any one hour which is as dark as, or darker than, Ringelmann 1 or 20% opacity. [District Rule 4101]
- 3. {98} No air contaminant shall be released into the atmosphere which causes a public nuisance. [District Rule 4102]
- 4. {1898} The exhaust stack shall vent vertically upward. The vertical exhaust flow shall not be impeded by a rain cap (flapper ok), roof overhang, or any other obstruction. [District Rule 4102]
- 5. {4257} This engine shall be equipped with an operational non-resettable elapsed time meter or other APCO approved alternative. [District Rule 4702, 17 CCR 93115, and 40 CFR 60 Subpart IIII]
- 6. {4258} Only CARB certified diesel fuel containing not more than 0.0015% sulfur by weight is to be used. [District Rules 2201 and 4801, 17 CCR 93115, 40 CFR Part 60 Subpart IIII]
- 7. Emissions from this IC engine shall not exceed any of the following limits: 3.8 g-NOx/bhp-hr, 1.0 g-CO/bhp-hr, or 0.2 g-VOC/bhp-hr. [District Rule 2201, 17 CCR 93115, and 40 CFR Part 60 Subpart IIII]
- 8. Emissions from this IC engine shall not exceed 0.11 g-PM10/bhp-hr based on USEPA certification using ISO 8178 test procedure. [District Rules 2201 and 4102, 17 CCR 93115, and 40 CFR Part 60 Subpart IIII]
- 9. {4261} This engine shall be operated and maintained in proper operating condition as recommended by the engine manufacturer or emissions control system supplier. [District Rule 4702 and 40 CFR 60 Subpart IIII]

CONDITIONS CONTINUE ON NEXT PAGE

YOU MUST NOTIFY THE DISTRICT COMPLIANCE DIVISION AT (559) 230-5950 WHEN CONSTRUCTION IS COMPLETED AND PRIOR TO OPERATING THE EQUIPMENT OR MODIFICATIONS AUTHORIZED BY THIS AUTHORITY TO CONSTRUCT. This is NOT a PERMIT TO OPERATE. Approval or denial of a PERMIT TO OPERATE will be made after an inspection to verify that the equipment has been constructed in accordance with the approved plans, specifications and conditions of this Authority to Construct, and to determine if the equipment can be operated in compliance with all Rules and Regulations of the San Joaquin Valley Unified Air Pollution Control District. Unless construction has commenced pursuant to Rule 2050, this Authority to Construct shall expire and application shall be cancelled two years from the date of issuance. The applicant is responsible for complying with all laws, ordinances and regulations of all-other governmental agencies which may pertain to the above equipment.

Seyed Sadredin, Executive Directory APCO

DAVID WARNER, Director of Permit Services

- 10. {3478} During periods of operation for maintenance, testing, and required regulatory purposes, the permittee shall monitor the operational characteristics of the engine as recommended by the manufacturer or emission control system supplier (for example: check engine fluid levels, battery, cables and connections; change engine oil and filters; replace engine coolant; and/or other operational characteristics as recommended by the manufacturer or supplier). [District Rule 4702]
- 11. {3807} An emergency situation is an unscheduled electrical power outage caused by sudden and reasonably unforeseen natural disasters or sudden and reasonably unforeseen events beyond the control of the permittee. [District Rule 4702]
- 12. {3808} This engine shall not be used to produce power for the electrical distribution system, as part of a voluntary utility demand reduction program, or for an interruptible power contract. [District Rule 4702]
- 13. {3496} The permittee shall maintain monthly records of emergency and non-emergency operation. Records shall include the number of hours of emergency operation, the date and number of hours of all testing and maintenance operations, the purpose of the operation (for example: load testing, weekly testing, rolling blackout, general area power outage, etc.) and records of operational characteristics monitoring. For units with automated testing systems, the operator may, as an alternative to keeping records of actual operation for testing purposes, maintain a readily accessible written record of the automated testing schedule. [District Rule 4702 and 17 CCR 93115]
- 14. {4262} This engine shall be operated only for testing and maintenance of the engine, required regulatory purposes, and during emergency situations. Operation of the engine for maintenance, testing, and required regulatory purposes shall not exceed 50 hours per calendar year. [District Rule 4702, 17 CCR 93115 and 40 CFR Part 60 Subpart IIII]
- 15. {4263} The permittee shall maintain monthly records of the type of fuel purchased. [District Rule 4702 and 17 CCR 93115]
- 16. {3475} All records shall be maintained and retained on-site for a minimum of five (5) years, and shall be made available for District inspection upon request. [District Rule 4702 and 17 CCR 93115]



Appendix B BACT Guideline and BACT Analysis

San Joaquin Valley Unified Air Pollution Control District

Best Available Control Technology (BACT) Guideline 3.1.1
Last Update: 7/10/2009
Emergency Diesel IC Engine

Pollutant	Achieved in Practice or in the SIP	Technologically Feasible	Alternate Basic Equipment
СО	Latest EPA Tier Certification level for applicable horsepower range		
NOX	Latest EPA Tier Certification level for applicable horsepower range		
PM10	0.15 g/hp-hr or the Latest EPA Tier Certification level for applicable horsepower range, whichever is more stringent. (ATCM)		
SOX	Very low sulfur diesel fuel (15 ppmw sulfur or less)		
VOC	Latest EPA Tier Certification level for applicable horsepower range		

BACT is the most stringent control technique for the emissions unit and class of source. Control techniques that are not achieved in practice or contained in a state implementation plan must be cost effective as well as feasible. Economic analysis to demonstrate cost effectiveness is required for all determinations that are not achieved in practice or contained in an EPA approved State Implementation Plan.

Top Down BACT Analysis for the Emergency IC Engine

BACT Guideline 3.1.1 (July 10, 2009) applies to emergency diesel IC engines. In accordance with the District BACT policy, information from that guideline will be utilized without further analysis.

1. BACT Analysis for NO_X and VOC Emissions:

a. Step 1 - Identify all control technologies

BACT Guideline 3.1.1 identifies only the following option:

Latest EPA Tier Certification level for applicable horsepower range

To determine the latest applicable Tier level, the following EPA and state regulations were consulted:

- 40 CFR Part 60 Subpart IIII Standards of Performance for Stationary Compression Ignition Internal Combustion Engines
- 40 CFR Part 89 Control of Emissions from New and In-Use Nonroad Compression Ignition Engines
- 40 CFR Part 1039 Control of Emissions from New and In-Use Nonroad Compression-Ignition Engines
- Title 17 CCR, Section 93115 Airborne Toxic Control Measure (ATCM) for Stationary Compression-Ignition (CI) Engines

40 CFR Parts 89 and 1039, which apply only to nonroad engines, do not directly apply because the proposed emergency engine(s) do not meet the definition of a nonroad engine. Therefore, only Title 17 CCR, Section 93115 and 40 CFR Part 60 Subpart IIII apply directly to the proposed emergency engine(s).

Title 17 CCR, Section 93115.6(a)(3)(A) (CARB stationary diesel engine ATCM) applies to emergency standby diesel-fired engines and requires that such engines be certified to the emission levels in Table 1 (below). Please note that these levels are at least as stringent or more stringent than the emission levels in 40 CFR Subpart IIII.

Table 1: Emission	Table 1: Emission Standards for New Stationary Emergency Standby Diesel-Fueled Cl Engines g/bhp-hr (g/kW-hr)											
Maximum Engine Power	Tier	Model Year(s)	PM	NMHC+NOx	СО							
50 ≤ HP < 75	2	2007	0.15 (0.20)	5.6 (7.5)	3.7 (5.0)							
(37 ≤ kW < 56)	4i	2008+	0.13 (0.20)	3.5 (4.7)	3.7 (3.0)							
75 ≤ HP < 100	2	2007	0.15 (0.20)	5.6 (7.5)	3.7 (5.0)							
$(56 \le kW < 75)$	3	2008+	0.13 (0.20)	3.5 (4.7)	3.7 (3.0)							
100 ≤ HP < 175	3	2007	0.15 (0.20)	3.0 (4.0)	3.7 (5.0)							
(75 ≤ kW < 130)	3	2008+	7 0.13 (0.20)	3.0 (4.0)	3.7 (3.0)							
175 ≤ HP < 300	3	2007	0.15 (0.20)	2.0 (4.0)	26 (25)							
(130 ≤ kW < 225)	3	2008+	0.15 (0.20)	3.0 (4.0)	2.6 (3.5)							
300 ≤ HP < 600	3	2007	0.15 (0.20)	2.0 (4.0)	26/25)							
(225 ≤ kW < 450)	3	2008+	7 0.15 (0.20)	3.0 (4.0)	2.6 (3.5)							
600 ≤ HP <u><</u> 750	3	2007	0.15 (0.20)	3.0.(4.0)	2.6 /2.5)							
$(450 \le kW \le 560)$	<u> </u>	2008+	0.15 (0.20)	3.0 (4.0)	2.6 (3.5)							
HP > 750	2	2007	0.15 (0.20)	19/6/1	26/25)							
(kW > 560)	2	2008+	0.15 (0.20)	4.8 (6.4)	2.6 (3.5)							

Additionally, 40 CFR Subpart IIII establishes emission standards for emergency diesel IC engines. These emission standards are the same as those specified in the CARB ATCM, except for engines rated greater than or equal to 50 and less than 75 hp. For such IC engines, the CARB ATCM is more stringent.

Therefore, the most stringent applicable emission standards are those listed in the CARB ATCM (Table 1).

For IC engines rated greater than or equal to 50 hp and less than 75 hp the the higherst Tier required is Tier 4i. For IC engines rated greater than or equal to 75 hp and less than 750 hp the highest Tier required is Tier 3. For engines rated equal to or greater than 750 hp the highest Tier required is Tier 2.

Also, please note that neither the state ATCM nor the Code of Federal Regulations require the installation of IC engines meeting a higher Tier standard than those listed above for emergency applications, due to concerns regarding the effectiveness of the exhaust emissions controls during periods of short-term operation (such as testing operational readiness of an emergency engine).

The proposed engine is rated at 2,722 hp. Therefore, the applicable control technology option is EPA Tier 2 certification.

b. Step 2 - Eliminate technologically infeasible options

The control option listed in Step 1 is not technologically infeasible.

c. Step 3 - Rank remaining options by control effectiveness

No ranking needs to be done because there is only one control option listed in Step 1.

d. Step 4 - Cost Effectiveness Analysis

The applicant has proposed the only control option remaining under consideration. Therefore, a cost effectiveness analysis is not required.

e. Step 5 - Select BACT

BACT for NOx and VOC will be the use of an EPA Tier 2 certified engine. The applicant is proposing such a unit. Therefore, BACT will be satisfied.

2. BACT Analysis for PM₁₀ Emissions:

a. Step 1 - Identify all control technologies

BACT Guideline 3.1.1 identifies only the following option:

 0.15 g/bhp-hr or the Latest EPA Tier Certification level for applicable horsepower range, whichever is more stringent. (ATCM)

The latest EPA Tier Certification level for an engine of the proposed model year and horsepower rating is Tier 2. Refer to the Top-Down BACT analysis for NOx for a discussion regarding the determination of the EPA Tier level to be considered.

Please note Tier 2 or 3 IC engines do not have a PM emission standard that is more stringent than 0.15 g/hp-hr. Additionally, the ATCM requires a PM emission standard of 0.15 g/hp-hr for all new emergency diesel IC engines.

Therefore, a PM/PM10 emission standard of 0.15 g/hp-hr is required as BACT.

b. Step 2 - Eliminate technologically infeasible options

The control option listed in Step 1 is not technologically infeasible.

c. Step 3 - Rank remaining options by control effectiveness

No ranking needs to be done because there is only one control option listed in Step 1.

d. Step 4 - Cost Effectiveness Analysis

The applicant has proposed the only control option remaining under consideration. Therefore, a cost effectiveness analysis is not required.

e. Step 5 - Select BACT

BACT for PM10 is emissions of 0.15 g/hp-hr or less. The applicant is proposing an engine that meets this requirement. Therefore, BACT will be satisfied.

Appendix C Emissions Data Sheet



CATERPILLAR INC.

EXECUTIVE ORDER U-R-001-0401 New Off-Road Compression-Ignition Engines

Pursuant to the authority vested in the Air Resources Board by Sections 43013, 43018, 43101, 43102, 43104 and 43105 of the Health and Safety Code; and

Pursuant to the authority vested in the undersigned by Sections 39515 and 39516 of the Health and Safety Code and Executive Order G-02-003:

IT IS ORDERED AND RESOLVED: That the following compression-ignition engine and emission control system produced by the manufacturer are certified as described below for use in off-road equipment. Production engines shall be in all material respects the same as those for which certification is granted.

MODEL YEAR	ENGINE FAMILY	DISPLACEMENT (liters)	FUEL TYPE	USEFUL LIFE (hours)
2010	ACPXL78.1T2X	78.1	Diesel	8000
SPECIAL	FEATURES & EMISSION		TYPICAL EQUIPMENT APPLIC	ATION
Direct Diesel Injection, Turbocharger, Charge Air Cooler, Smoke Puff Limiter and Engine Control Module			Generator	

The engine models and codes are attached.

The following are the exhaust certification standards (STD) and certification levels (CERT) for hydrocarbon (HC), oxides of nitrogen (NOx), or non-methane hydrocarbon plus oxides of nitrogen (NMHC+NOx), carbon monoxide (CO), and particulate matter (PM) in grams per kilowatt-hour (g/kw-hr), and the opacity-of-smoke certification standards and certification levels in percent (%) during acceleration (Accel), lugging (Lug), and the peak value from either mode (Peak) for this engine family (Title 13, California Code of Regulations, (13 CCR) Section 2423):

Γ	RATED EMISSION				EXHAUST (g/kw-hr)					OPACITY (%)		
	POWER CLASS	STANDARD CATEGORY		НС	NOx	NMHC+NOx	co	PM	ACCEL	LUG	PEAK	
	KW > 560	Tier 2	STD	N/A	N/A	6.4	3.5	0.20	N/A	N/A	N/A	
			CERT		_	5.4	1.4	0.15		-		

9/blp-lu 4.0 1.0 0.11

BE IT FURTHER RESOLVED: That for the listed engine models, the manufacturer has submitted the information and materials to demonstrate certification compliance with 13 CCR Section 2424 (emission control labels), and 13 CCR Sections 2425 and 2426 (emission control system warranty).

Engines certified under this Executive Order must conform to all applicable California emission regulations.

This Executive Order is only granted to the engine family and model-year listed above. Engines in this family that are produced for any other model-year are not covered by this Executive Order.

Executed at El Monte, California on this __

day of December 2009.

Annette Hebert, Chief

Mobile Source Operations Division

Engine Model Summary Template

ATTACHMENT 1 OF 1

U-R-001-0401 12/08/09

Engine Family	1.Engine Code	2.Engine Model	3.BHP@RPM (SAE Gross)	4.Fuel Rate: mm/stroke @ peak HP (for diesel only)	5.Fuel Rate: (lbs/hr) @ peak HP (for diesels only)	6.Torque @ RPM (SEA Gross)	7.Fuel Rate: mm/stroke@peak torque	(lbs/hr)@peak torque	9.Emission Control Device Per SAE J1930
ACPXL78.1T2X	11	3516C	2150@1200	690.0	743.0	9403@1200	NA	NA SPL	ر EM,DI,TC,ECM
ACPXL78.1T2X	2	3516C	1855@1200	589.8	635.0	8113@1200	NA	NA n	EM,DI,TC,ECM
ACPXL78.1T2X	3	3516C	2722@1800	560	904	7942@1800	NA	NA 11	EM,DI,TC,ECM
ACPXL78.1T2X	4	3516C	2100@1500	521.5	694	7353@1500	NA	NA "	EM,DI,TC,ECM
ACPXL78.1T2X	5	3516C	2602@1800	556.5	898.9	7591@1800	NA	NA u	EM,DI,TC,ECM

Engine Model Summary Template

ATTACHMENT 1 OF 1

U-R-001-0401 12/16/10

				4.Fuel Rate:	5.Fuel Rate:		7.Fuel Rate:		
Engine Family	1.Engine Code	2.Engine Model	3.BHP@RPM (SAE Gross)	mm/stroke @ peak HP (for diesel only)	(lbs/hr) @ peak HP (for diesels only)	6.Torque @ RPM (SEA Gross)	mm/stroke@peak torque	8.Fuel Rate: (lbs/hr)@peak torque	9.Emission Control Device Per SAE J1930
ACPXL78.1T2X	1	3516C	2150@1200	690.0	743.0	9403@1200	NA	NA	EM,DI,TC,ECM
ACPXL78.1T2X	2	3516C	1855@1200	589.8	635.0	8113@1200	NA	NA	EM,DI,TC,ECM
ACPXL78.1T2X	3	3516C	2722@1800	560	904	7942@1800	NA	NA	EM,DI,TC,ECM
ACPXL78.1T2X	4	3516C	1926@1500	516.1	694.4	6743@1500	NA	NA	EM,DI,TC,ECM
ACPXL78.1T2X	5	3516C	2602@1800	556.5	898.9	7591@1800	NA	NA	EM,DI,TC,ECM

Appendix D HRA Summary and AAQA

San Joaquin Valley Air Pollution Control District Risk Management Review

To: Sajjad Ahmad - Permit Services

From: Kyle Melching - Permit Services

Date: June 25, 2013

Facility Name: Central Cal Women's Facility

Location: 23370 Road 22

Application #(s): C-252-23-0

Project #: C-1131956

A. RMR SUMMARY

RMR Summary									
Categories Emergency Diesel ICE Project Totals Facility Totals (Unit 23-0)									
Prioritization Score	N/A ¹	N/A ¹	>1						
Acute Hazard Index	N/A ²	N/A ²	N/A						
Chronic Hazard Index	N/A ²	N/A ²	N/A						
Maximum Individual Cancer Risk	1.2E-07	1.2E-07	1.2E-07						
T-BACT Required?	No								
Special Permit Conditions?	Yes								

¹ Prioritization for this unit was not conducted since it has been determined that all diesel-fired IC engines will result in a prioritization score greater than 1.0.

Proposed Permit Conditions

To ensure that human health risks will not exceed District allowable levels; the following permit conditions must be included for:

Unit 23-0

- 1. The PM10 emissions rate shall not exceed **0.11** g/bhp-hr based on US EPA certification using ISO 8178 test procedure. [District Rules 2201]
- 2. The exhaust stack shall vent vertically upward. The vertical exhaust flow shall not be impeded by a rain cap (flapper ok), roof overhang, or any other obstruction. [District Rule 4102]
- This engine shall be operated only for testing and maintenance of the engine, required regulatory purposes, and during emergency situations. Operation of the engine for maintenance, testing, and required regulatory purposes shall not exceed 50 hours per calendar year. [District Rule 4702 and 17 CCR 93115]

Acute and Chronic Hazard Indices were not calculated since there is no risk factor, or the risk factor is so low that the risk has been determined to be insignificant for this type of unit.

B. RMR REPORT

Project Description

Technical Services received a request on June 21, 2013, to perform an Ambient Air Quality Analysis (AAQA) and a Risk Management Review (RMR) for one 2,722 bhp emergency diesel IC engine powering an electrical generator.

II. **Analysis**

Technical Services performed screening level health risk assessments using the District developed DICE database.

The following parameters were used for the review:

Analysis Parameters Unit 23-0									
Source Type Point Location Type Rural									
ВНР	2,722	PM ₁₀ g/hp-hr	0.11						
Closest Receptor (m)	1402	Quad	2						
Max Hours per Year	50	Type of Closest Receptor	Business						

Technical Services also performed modeling for criteria pollutants NOx, SOx, PM₁₀, and PM_{2.5}; as well as the RMR. For Unit 1-0, the emission rates used for criteria pollutant modeling were 1,140 lb/yr NOx, 2 lb/yr SOx, 33 lb/yr PM₁₀, and 33 lb/yr PM_{2.5}.

The results from the Criteria Pollutant Modeling are as follows:

Criteria Pollutant Modeling Results*

Diesel ICE	1 Hour	3 Hours	8 Hours	24 Hours	Annual
CO	NA ¹	X	NA ¹	Χ	X
NO _x	NA ¹	Х	X	X	Pass
SO _x	NA ¹	NA ¹	Х	NA ¹	Pass
PM ₁₀	X	Х	X	NA ¹	Pass ²
PM _{2.5}	X	X	X	NA ¹	Pass ²

^{*}Results were taken from the attached PSD spreadsheet.

III. Conclusions

The emissions from the proposed equipment will not cause or contribute significantly to a violation of the State and National AAQS.

The cancer risk associated with the operation of the proposed diesel IC engine is 1.2E-07; which is less than 1.0 in a million. In accordance with the District's Risk Management Policy, the project is approved without Toxic Best Available Control Technology (T-BACT) for PM10.

¹The project is an intermittent source as defined in APR-1920. In accordance with APR-1920, compliance with shortterm (i.e., 1-hour, 3-hour, 8-hour, and 24-hour) standards is not required.
²The criteria pollutants are below EPA's level of significance as found in 40 CFR Part 51.165 (b)(2).

Central Cal Women's Facility; C-252, C-1131956 Page 3 of 3

To ensure that human health risks will not exceed District allowable levels; the permit conditions listed on page 1 of this report must be included for the proposed unit.

These conclusions are based on the data provided by the applicant and the project engineer. Therefore, this analysis is valid only as long as the proposed data and parameters do not change.

IV. Attachments

- A. RMR request from the project engineer
- B. Additional information from the applicant/project engineer
- C. Stack Parameter Worksheet
- D. DICE Screening Risk Tool
- E. Facility Summary
- F. AAQA Summary
- G. AERMOD Non-Regulatory Checklist

Appendix E QNEC Calculations

Quarterly Net Emissions Change (QNEC)

The Quarterly Net Emissions Change is used to complete the emission profile screen for the District's PAS database. The QNEC shall be calculated as follows:

QNEC = PE2 - PE1, where:

QNEC = Quarterly Net Emissions Change for each emissions unit, lb/qtr

PE2 = Post-Project Potential to Emit for each emissions unit, lb/qtr

PE1 = Pre-Project Potential to Emit for each emissions unit, lb/gtr

Since this is a new unit, PE1 = 0 for all pollutants. Thus, QNEC = PE2 (lb/qtr).

Using the PE2 (lb/yr) values calculated in Section VII.C.2, Quarterly PE2 is calculated as follows:

PE2_{quarterly} = PE2 (lb/yr) ÷ 4 quarters/year = QNEC

QNEC		
Pollutant	PE2 Total (lb/yr)	Quarterly PE2 (lb/qtr)
NO _x	1,140	285.0
SO _x	2	0.5
PM ₁₀	33	8.3
СО	300	75.0
VOC	60	15.0